REPORT RESUMES

ED 019 845 EF 001 815

KENTUCKY PUBLIC SCHOOL CONSTRUCTION.

BY- SPARKS, HARRY M.

KENTUCKY STATE DEPT. OF EDUCATION, FRANKFORT

PUB DATE 67

EDRS PRICE MF-$0.75 HC-$7.44 184P.

DESCRIPTORS- *SCHOOL ARCHITECTURE, *SCHOOL BUILDINGS, *SCHOOL CONSTRUCTION, *SCHOOL DISTRICT SPENDING, ELEMENTARY SCHOOLS, HIGH SCHOOLS, SCHOOL SUPPORT,

NEW SCHOOL CONSTRUCTION IN THE STATE OF KENTUCKY IS ILLUSTRATED THROUGH REVIEW OF--(1) 15 ELEMENTARY SCHOOLS, (2) 14 HIGH SCHOOLS, AND (3) ONE ADMINISTRATIVE FACILITY. EACH EXAMPLE INCLUDES--(1) A GENERAL ARCHITECTURAL DESCRIPTION, (2) SITE AND FLOOR PLANS, AND (3) AN EXTERIOR PHOTOGRAPH OR PERSPECTIVE. PRECEDING THESE EXAMPLES ARE REVIEWS OF--(1) BONDS, SPECIAL LEVIES AND ASSESSMENTS OF STATE SCHOOL DISTRICTS, (2) BONDS OUTSTANDING AND SCHOOL REVENUE BONDS, AND (3) AREA AND COST DATA FOR SCHOOL CONSTRUCTION. COPIES MAY ALSO BE OBTAINED FROM THE DIRECTOR, DIVISION OF STATISTICAL SERVICES, STATE DEPARTMENT OF EDUCATION, FRANKFORT, KENTUCKY. (MH)

U.S. DEPARTMENT OF HEALTH, EDUCATION & WELFARE
OFFICE OF EDUCATION

THIS DOCUMENT HAS BEEN REPRODUCED EXACTLY AS RECEIVED FROM THE PERSON OR ORGANIZATION ORIGINATING IT. POINTS OF VIEW OR OPINIONS STATED DO NOT NECESSARILY REPRESENT OFFICIAL OFFICE OF EDUCATION POSITION OR POLICY.

ED019845

Kentucky
Public School Construction



EF 001 815

Kentucky Department of Education
1967

Dr. Harry M. Sparks
Superintendent of Public Instruction

Kentucky

Public School Construction



COMMONWEALTH OF KENTUCKY
DEPARTMENT OF EDUCATION
FRANKFORT, KY. 40601

HARRY M. SPARKS
SUPERINTENDENT OF PUBLIC INSTRUCTION

January 1967

Schools in Kentucky have made tremendous strides in their efforts to improve public education. An outstanding example of the progress being made are the school facilities recently constructed. This bulletin presents the plans of the new school buildings constructed during the past three years.

The innovations and concepts incorporated in the schools presented in this bulletin can provide the school administrator a valuable source of ideas for planning and design of future school district construction.

Harry M. Sparks

Harry M. Sparks
Superintendent of Public Instruction

CONTENTS

Page

Foreword iii

Introduction iv

Bonds, Special Levies and Assessments of Kentucky School Districts 1

Bonds Outstanding 13

School Building Revenue Bonds sold July 1, 1965 through June 30, 1966 14

Area and Cost Data for Some of the 1965-66 School Construction 15

Architectural Materials Concerning Recent Construction in School Housing:

- Elementary Schools 18
- High Schools 77
- Administrative Buildings 146
- Vocational Schools 152

FOREWORD

The Commonwealth of Kentucky can be extremely proud of the many fine schools that have been constructed within recent years. Unfortunately, all school personnel do not have the opportunity to visit these plants to become acquainted with their many fine features. Second to a personal visit, would be viewing plans, analyzing costs and studying special problems involved in construction.

Planning for school construction is always confronting the school administrator. Even though funds may not be available for major construction at the present time, problems of school housing exists in all districts. Increased enrollment, shifting population, replacement of older buildings, expansion of curriculum and modernization of present facilities are but a few of the factors demanding new school plants.

The Division of Buildings and Grounds contacted the Division of Finance, State Department of Education, for current data concerning school building finance through the districts of Kentucky. This material has been reproduced in this bulletin for your use.

This Division also contacted architects, who have recently designed public school buildings throughout the state, in search of material to be used in this publication. We asked for information on buildings constructed since January of 1963. All drawings, sketches, photographs and individual data sheets were supplied by these architects and were reproduced, as submitted, for use in this bulletin.

With the above-mentioned material and information obtained from records in this office, we have assembled this publication. It is our sincere hope that this effort will be of some help to you in planning for future construction.

Division of Buildings and Grounds
Bureau of Administration and Finance
Kentucky State Department of Education

INTRODUCTION

The Division of Buildings and Grounds received 365 School Building Application forms for the year 1965-66. Many of these applications were for small additions, minor alternations, or renovations, temporary structures, etcetera. Some of these projects are still in the planning stage and specific data is not available at this time.

The following tables show the bonded indebtedness for the school districts of Kentucky and a compilation of the first twenty major construction projects for which contracts were let for construction.

KENTUCKY
DEPARTMENT OF EDUCATION
Bureau of Administration and Finance

Bonded Indebtedness of Kentucky School Districts as of June 30, 1966

Type of Issues; Sinking Fund Levy; Tax Rate Voted 1/ - Special Voted General Fund and Special Voted Building Fund; Assessment; Percentage of Total Assessment for Bonded Indebtedness

(1/ Rate voted by the people. For school years 1966-67 and 1967-68 this rate has been reduced to a compensating rate. See rate approved by State Board of Education for the 1966-67 Tax Levy.)

School District	Revenue Bonds	Funding Bonds	Voted Bonds	Sinking Fund Levy (1966-67)	Rate Voted Special Voted General Fund (KRS 157.440)	Date Tax Voted	Number of Years (I. Indefinite)	Rate Voted Special Voted Building Fund (KRS 160.477)	Date Tax Voted	Number of Years (I. Indefinite)	Total Assessment (1966-67) Excluding Bank Shares	Percentage of Total Assessment to Bonds Outstanding
Adair Co.	$1,088,000	$ -	$ -	$ -	$ -	-	-	$.05-.50	5-26-59	I.	$ 68,832,941	1.58%
Allen Co.	368,000	-	-	-	-	-	-	-	-	-	41,407,247	.89
Anderson Co.	942,000	-	-	-	-	-	-	-	-	-	72,051,142	1.31
Ballard Co.	512,000	-	-	-	-	-	-	-	-	-	44,948,184	1.14
Barren Co.	710,000	105,000	-	1.5 2/	-	-	-	-	-	-	88,781,840	.80
Bath Co.	562,000	-	-	-	-	-	-	-	-	-	60,769,037	.92
Bell Co.	1,052,000	-	-	-	-	-	-	-	-	-	32,297,812	3.26
Boone Co.	2,984,000	-	-	-	-	-	-	.05-.25	11-7-61	I.	153,504,820	1.94
Bourbon Co.	929,000	-	-	-	-	-	-	-	-	-	109,348,319	.85
Boyd Co.	1,478,000	-	-	-	-	-	-	.50	12-6-55	25	73,377,901	2.01
Boyle Co.	1,394,000	-	-	-	-	-	-	.05-.50	4-29-61	20	59,881,247	2.33
Bracken Co.	181,000	-	-	-	-	-	-	-	-	-	36,431,578	.50
Breathitt Co.	1,037,000	-	-	-	-	-	-	-	-	-	21,329,611	4.86

2/ Funding Bond Levy

School District	Revenue Bonds	Funding Bonds	Voted Bonds	Sinking Fund Levy (1966-67)	Rate Voted Special Voted General Fund (KRS 157.440)	Date Tax Voted	Number of Years (I. Indefinite)	Rate Voted Special Voted Building Fund (KRS 160.477)	Date Tax Voted	Number of Years (I. Indefinite)	Total Assessment (1966-67) Excluding Bank Shares	Percentage of Total Assessment to Bonds Outstanding
Breckinridge Co.	$1,309,000	$ -	$ -	$ -	$ -	-	-	$.05-.50	5-28-63	20	$ 63,478,502	2.06%
Bullitt Co.	1,735,000	-	-	-	-	-	-	-	-	-	164,865,984	1.05
Butler Co.	407,000	-	-	-	-	-	-	-	-	-	37,525,187	1.08
Caldwell Co.	570,000	-	-	-	-	-	-	-	-	-	62,805,634	.91
Calloway Co.	654,000	-	-	-	-	-	-	-	-	-	58,608,288	1.12
Campbell Co.	2,544,000	-	-	-	-	-	-	.05-.50	11-4-58	I.	123,624,577	2.06
Carlisle Co.	185,000	-	-	-	-	-	-	-	-	-	31,132,964	.59
Carroll Co.	946,000	-	-	-	.70	3-3-62	I.	-	-	-	45,967,065	2.06
Carter Co.	687,000	-	-	-	-	-	-	-	-	-	69,810,243	.98
Casey Co.	644,000	-	-	-	-	-	-	-	-	-	54,092,220	1.19
Christian Co. (Pembroke)[3]	1,833,000	-	-	-	-	-	-	- .05-.50	- 6-1-55	- 25	126,728,637	1.45
Clark Co.	2,150,000	-	-	-	-	-	-	.05-.50[4]	4-7-59	20	151,498,800	1.42
Clay Co.	-0-	-	-	-	-	-	-	-	-	-	33,080,057	-
Clinton Co.	487,000	-	-	-	-	-	-	-	-	-	30,199,067	1.47
Crittenden Co.	437,000	-	-	-	-	-	-	-	-	-	35,102,590	1.24
Cumberland Co.	318,000	-	-	-	-	-	-	-	-	-	26,637,070	1.19
Daviess Co.	1,949,000	-	-	-	-	-	-	-	-	-	277,974,306	.70

3/ Merged with county, Special Voted Building Tax applies to Pembroke only.

4/ Winchester merged with county, $.50 Special Voted Building Fund still applies, KRS 160.477, voted 11-2-54 for 20 years.

School District	Revenue Bonds	Funding Bonds	Voted Bonds	Sinking Fund Levy (1966-67)	Rate Voted Special Voted General Fund (KRS 157.440)	Date Tax Voted	Number of Years (I. Indefinite)	Rate Voted Special Voted Building Fund (KRS 160.477)	Date Tax Voted	Number of Years (I. Indefinite)	Total Assessment (1966-67) Excluding Bank Shares	Percentage of Total Assessment to Bonds Outstanding
Edmonson Co.	$ 247,000	$ -	$ -	$ -	$ -	-	-	-	-	-	$ 30,510,547	.81%
Elliott Co.	272,000	-	-	-	-	-	-	-	-	-	15,596,427	1.74
Estill Co.	358,000	-	-	-	-	-	-	-	-	-	28,608,484	1.25
Fayette Co.	16,114,000	-	-	-	.50	5-29-62	I.	.32	4-18-51	25[5/]	811,539,866	1.99
Fleming Co.	522,000	-	-	-	-	-	-	-	-	-	56,779,687	.92
Floyd Co. (Prestonsburg)[6/]	1,631,000	-	-	-	-	-	-	- .05-.35	- 3-26-54	- 25	117,347,108	1.39
Franklin Co.	1,195,000	-	-	-	-	-	-	-	-	-	204,170,469	.59
Fulton Co.	495,000	-	-	-	.50	11-8-60	I.	-	-	-	37,227,644	1.33
Gallatin Co.	242,000	-	-	-	-	-	-	-	-	-	21,192,119	1.14
Garrard Co.	1,605,000	-	-	-	.50	4-15-61	I.	-	-	-	76,233,368	2.11
Grant Co.	966,000	-	-	-	-	-	-	.50	5-28-57	I.	46,756,690	2.07
Graves Co.	989,000	-	-	-	-	-	-	-	-	-	89,011,118	1.11
Grayson Co.	185,000	-	-	-	-	-	-	-	-	-	45,941,517	.40
Green Co.	589,000	-	-	-	-	-	-	.05-.50	5-23-61	I.	57,419,755	1.03
Greenup Co.	1,522,000	60,000	-	-	-	-	-	.50[11/]	10-2-54	I.	68,789,323	2.21
Hancock Co.	414,000	-	-	-	-	-	-	.05-.50	11-3-59	I.	34,430,306	1.20

5/ January 12, 1957, Fayette County voted to extend its Special Voted Building Fund Tax from 20 years to 25 years.
6/ Merged with county, Special Voted Building Fund applies to Prestonsburg only.
11/ Special Voted General Fund, KRS 160.477, $.50 voted 2-26-55 for indefinite period.

School District	Revenue Bonds	Funding Bonds	Voted Bonds	Sinking Fund Levy (1966-67)	Rate Voted Special Voted General Fund (KRS 157.440)	Date Tax Voted	Number of Years (I. Indefinite)	Rate Voted Special Voted Building Fund (KRS 160.477)	Date Tax Voted	Number of Years (I. Indefinite)	Total Assessment (1966-67) Excluding Bank Shares	Percentage of Total Assessment to Bonds Outstanding
Hardin Co.	$ 1,576,000	$ -	$ -	$ -	$ -	-	-	$ -	-	-	$125,937,461	1.25%
Harlan Co.	2,147,000	-	-	-	-	-	-	-	-	-	67,449,798	3.18
Harrison Co.	2,318,000	-	-	-	-	-	-	.05-.50	5-29-62	I.	94,835,169	2.44
Hart Co.	476,000	-	-	-	-	-	-	.05-.20	4-23-56	I.	57,358,995	.83
Henderson Co.	1,722,000	-	-	-	-	-	-	.05-.50	5-27-58	I.	137,126,545	1.26
Henry Co.	1,182,000	-	-	-	-	-	-	.05-.50	3-25-61	I.	49,584,300	2.38
Hickman Co.	337,000	-	-	-	-	-	-	-	-	-	41,425,132	.81
Hopkins Co.	2,274,000	-	-	-	.50	2-26-60	I.	-	-	-	183,563,912	1.24
Jackson Co.	781,000	-	-	-	-	-	-	-	-	-	24,557,755	3.18
Jefferson Co.	29,277,000	-	-	-	-	-	-	.05-.50	11-4-52	20	2,534,492,352	1.16
Jessamine Co.	700,000	-	-	-	-	-	-	-	-	-	97,520,668	.72
Johnson Co.	561,000	-	-	-	.75	2-9-65	I.	-	-	-	33,824,322	1.66
Kenton Co.	5,477,000	-	-	-	-	-	-	.50	5-28-57	I.	234,666,933	2.33
Knott Co.	519,000	-	-	-	-	-	-	-	-	-	44,855,871	1.16
Knox Co.	813,000	-	-	-	-	-	-	-	-	-	35,607,463	2.28
LaRue Co.	1,025,000	-	-	-	-	-	-	.30	3-29-59	20	57,598,626	1.78
Laurel Co.	742,000	-	-	-	-	-	-	-	-	-	69,208,120	1.07

School District	Revenue Bonds	Funding Bonds	Voted Bonds	Sinking Fund Levy (1966-67)	Rate Voted Special Voted General Fund (KRS 157.440)	Date Tax Voted	Number of Years (I Indefinite)	Rate Voted Special Voted Building Fund (KRS 160.477)	Date Tax Voted	Number of Years (I. Indefinite)	Total Assessment (1966-67) Excluding Bank Shares	Percentage of Total Assessment to Bonds Outstanding
Lawrence Co.	$ 597,000	$ -	$ -	$ -	$ -	-	-	$ -	-	-	$ 47,906,383	1.25%
Lee Co.	628,000	-	-	-	-	-	-	.40	5-29-62	20	28,499,715	2.20
Leslie Co.	645,000	-	-	-	-	-	-	-	-	-	27,181,889	2.37
Letcher Co.	1,441,000	-	-	-	-	-	-	-	-	-	53,299,742	2.70
Lewis Co.	1,196,000	-	-	-	-	-	-	.05-.50	5-26-59	I.	55,775,117	2.14
Lincoln Co.	915,000	-	-	-	-	-	-	-	-	-	92,781,790	.99
(Stanford) 7/								.05-.50	3-10-56	20		
Livingston Co.	517,000	-	-	-	-	-	-	-	-	-	31,541,796	1.64
Logan Co.	524,000	12,000	-	-	-	-	-	-	-	-	67,232,538	.78
Lyon Co.	490,000	-	-	-	-	-	-	.05-.50	9-6-62	22	33,471,049	1.46
Madison Co.	1,242,000	-	-	-	-	-	-	-	-	-	120,602,525	1.03
Magoffin Co.	632,000	-	-	-	-	-	-	-	-	-	34,258,084	1.84
Marion Co.	939,000	-	-	-	-	-	-	-	-	-	87,261,728	1.08
Marshall Co.	1,143,000	-	-	-	-	-	-	.35	10-5-56	20	96,951,224	1.18
Martin Co.	393,000	-	-	-	-	-	-	-	-	-	29,814,872	1.32
Mason Co.	1,416,000	-	-	-	-	-	-	.05-.38	2-24-62	25	68,797,150	2.06
McCracken Co.	2,360,000	-	-	-	-	-	-	.05-.50	4-11-53	22	113,409,744	2.08
McCreary Co.	382,000	-	-	-	-	-	-	-	-	-	25,175,338	1.52

7/ Merged with county, Special Voted Building Fund applies to Stanford only.

School District	Revenue Bonds	Funding Bonds	Voted Bonds	Sinking Fund Levy (1966-67)	Rate Voted Special Voted General Fund (KRS 157.440)	Date Tax Voted	Number of Years (I. Indefinite)	Rate Voted Special Voted Building Fund (KRS 160.477)	Date Tax Voted	Number of Years (I. Indefinite)	Total Assessment (1966-67) Excluding Bank Shares	Percentage of Total Assessment to Bonds Outstanding
McLean Co.	$ 396,000	$ -	$ -	$ -	$ -	-	-	$ -	-	-	$ 56,231,625	.70%
Meade Co.	1,163,000	-	-	-	-	-	-	.05-.50	2-14-59	I.	60,042,677	1.94
Menifee Co.	338,000	-	-	-	-	-	-	-	-	-	15,257,206	2.22
Mercer Co.	289,000	-	-	-	-	-	-	-	-	-	58,452,884	.49
Metcalfe Co.	578,000	56,000	-	-	-	-	-	.50	5-8-58	20	39,279,830	1.47
Monroe Co.	811,000	60,000	-	-	-	-	-	.05-.50	3-12-63	20	49,587,174	1.64
Montgomery Co.	1,298,000	-	-	-	-	-	-	.05-.50	5-29-62	25	66,334,912	1.96
Morgan Co.	169,000	-	-	-	-	-	-	-	-	-	32,023,888	.53
Muhlenberg Co.	1,168,000	-	-	-	-	-	-	-	-	-	100,029,970	1.17
Nelson Co.	432,000	-	-	-	-	-	-	-	-	-	150,510,910	.29
Nicholas Co.	493,000	-	-	-	-	-	-	-	-	-	35,370,241	1.39
Ohio Co.	1,450,000	-	-	-	-	-	-	-	-	-	83,894,633	1.73
Oldham Co.	2,662,000	-	-	-	.44	5-26-64	I.	.05-.50	6-22-57	I.	83,603,770	3.18
Owen Co.	411,000	-	-	-	-	-	-	-	-	-	50,713,290	.81
Owsley Co.	221,000	-	-	-	-	-	-	-	-	-	11,227,825	1.96
Pendleton Co.	850,000	-	-	-	-	-	-	.05-.50	5-29-56	I.	35,508,810	2.39
Perry Co.	1,209,000	-	-	-	-	-	-	-	-	-	44,249,500	2.73
Pike Co.	-0-	-	-	-	-	-	-	-	-	-	202,381,856	-

School District	Revenue Bonds	Funding Bonds	Voted Bonds	Sinking Fund Levy (1966-67)	Rate Voted Special Voted General Fund (KRS 157.440)	Date Tax Voted	Number of Years (I. Indefinite)	Rate Voted Special Voted Building Fund (KRS 160.477)	Date Tax Voted	Number of Years (I. Indefinite)	Total Assessment (1966-67) Excluding Bank Shares	Percentage of Total Assessment to Bonds Outstanding
Powell Co.	$ 440,000	$ -	$ -	$ -	$ -	-	-	$ -	-	-	$ 29,751,460	1.48%
Pulaski Co.	1,144,000	-	-	-	-	-	-	-	-	-	78,025,060	1.47
Robertson Co.	253,000	-	-	-	-	-	-	.05-.50	5-21-61	30	11,145,755	2.27
Rockcastle Co.	247,000	-	-	-	-	-	-	-	-	-	37,684,365	.66
Rowan Co.	1,306,000	3,000	-	-	-	-	-	.05-.50	3-31-59	39	65,098,201	2.01
Russell Co.	628,000	-	-	-	-	-	-	-	-	-	44,221,631	1.42
Scott Co.	1,041,000	-	-	-	-	-	-	-	-	-	83,495,588	1.25
Shelby Co.	1,637,000	-	-	-	-	-	-	.05-.50	3-24-59	I.	78,221,621	2.09
Simpson Co.	790,000	-	-	-	-	-	-	.05-.25	4-28-55	20	81,132,623	.97
Spencer Co.	324,000	-	-	-	-	-	-	-	-	-	31,921,678	1.01
Taylor Co.	907,000	-	-	-	-	-	-	.50	1-5-60	20	54,118,621	1.68
Todd Co.	653,000	-	-	-	-	-	-	-	-	-	57,658,091	1.13
Trigg Co.	817,000	-	-	-	-	-	-	.05-.50	5-19-56	20	49,713,742	1.64
Trimble Co.	305,000	-	-	-	-	-	-	.05-.36	6-14-52	I.	29,865,552	1.02
Union Co.	2,319,000	-	-	-	-	-	-	.05-.50	11-9-61	20	93,001,754	2.49
Warren Co.	601,000	-	-	-	-	-	-	-	-	-	112,650,153	.53
Washington Co.	949,000	-	-	-	-	-	-	-	-	-	55,342,283	1.71
(Springfield)8/								.05-.50	3-10-56	I.		

8/ Merged with county, Special Voted Building Fund applies to Springfield only

School District	Revenue Bonds	Funding Bonds	Voted Bonds	Sinking Fund Levy (1966-67)	Rate Voted Special Voted General Fund (KRS 157.440)	Date Tax Voted	Number of Years (I. Indefinite)	Rate Voted Special Voted Building Fund (KRS 160.477)	Date Tax Voted	Number of Years (I. Indefinite)	Total Assessment (1966-67) Excluding Bank Shares	Percentage of Total Assessment to Bonds Outstanding
Wayne Co.	$ 357,000	$ -	$ -	$ -	$ -	-	-	$ -	-	-	$ 34,608,181	1.03%
Webster Co.	628,000	-	-	-	-	-	-	-	-	-	68,576,220	.92
Whitley Co.	849,000	-	-	-	-	-	-	-	-	-	33,929,240	2.50
Wolfe Co.	233,000	-	-	-	-	-	-	-	-	-	13,289,143	1.75
Woodford Co.	1,831,000	-	-	-	-	-	-	-	-	-	174,247,190	1.05
Anchorage	-0-	-	-	-	1.25	[9]	I.	-	-	-	13,959,750	-
Ashland	3,203,000	-	-	.07[10]	-	-	-	.50	6-25-57	20	52,504,444	6.10
Augusta	32,000	-	-	-	-	-	-	.25	5-21-55	I.	5,951,550	.54
Barbourville	97,000	-	-	-	-	-	-	-	-	-	10,348,765	.94
Bardstown	556,000	-	-	-	-	-	-	-	-	-	98,996,604	.56
Beechwood	-0-	-	-	-	-	-	-	-	-	-	36,604,701	-
Bellevue	540,000	-	-	-	-	-	-	-	-	-	28,373,112	1.90
Benton	350,000	-	-	-	-	-	-	.05-.50	3-7-53	I.	20,434,849	1.71
Berea	32,000	-	-	-	-	-	-	.45	12-8-65	I.	14,582,397	.22
Bowling Green	3,526,000	-	-	-	-	-	-	.35	5-27-58	30	145,328,313	2.43
Burgin	407,000	-	-	-	-	-	-	.05-.50	5-28-63	I.	13,202,204	3.08

[9] Special Voted General Fund, KRS 157.440, $.50 voted 11-6-56, $.75 voted 11-7-61 for indefinite period.

[10] For Ashland Junior College

School District	Revenue Bonds	Funding Bonds	Voted Bonds	Sinking Fund Levy (1966-67)	Rate Voted Special Voted General Fund (KRS 157.440)	Date Tax Voted	Number of Years (I. Indefinite)	Rate Voted Special Voted Building Fund (KRS 160.477)	Date Tax Voted	Number of Years (I. Indefinite)	Total Assessment (1966-67) Excluding Bank Shares	Percentage of Total Assessment to Bonds Outstanding
Campbellsville	$ 664,000	$ -	$ -	$ -	$ -	-	-	$.05-.50	9-11-51	I.	$ 32,039,761	2.07%
Catlettsburg	335,000	-	-	-	-	-	-	.05-.50	5-15-62	I.	13,669,954	2.45
Caverna	408,000	-	-	-	-	-	-	.50	11-7-50	23	24,129,074	1.69
Central City	155,000	-	12,000	.03	-	-	-	-	-	-	16,322,370	.95
Cloverport	130,000	-	-	-	-	-	-	.05-.50	4-12-55	I.	4,825,268	2.69
Corbin	594,000	-	-	-	-	-	-	.05-.50	2-11-58	I.	29,466,146	2.02
Covington	1,450,000	-	881,000	.06	.25	11-3-59	I.	-	-	-	92,413,168	1.57
Danville	2,397,000	-	-	-	.60	5-2-59	I.	.50	12-5-59	I.	66,803,917	3.59
Dawson Springs	93,000	-	-	-	-	-	-	.05-.50	11-4-52	I.	9,689,540	.96
Dayton	440,000	-	-	-	-	-	-	.50	5-24-52	I.	20,539,620	2.14
Earlington	242,000	-	-	-	-	-	-	.05-.50	11-15-56	25	8,458,125	2.86
East Bernstadt	75,000	-	-	-	-	-	-	-	-	-	2,700,890	2.78
Elizabethtown	1,089,000	-	-	-	-	-	-	.05-.50	12-15-53	I.	62,021,250	1.76
Eminence	300,000	-	-	-	-	-	-	.05-.50	3-18-53	I.	11,925,840	2.52
Erlanger	1,093,000	-	-	-	-	-	-	.05-.50	6-16-53	I.	70,509,966	1.55
Fairview	687,000	-	-	-	1.00	2-27-60	I.	.05-.50	6-10-55	20	25,174.559	2.73
Falmouth	70,000	-	-	-	-	-	-	-	-	-	11,821,632	.59

School District	Revenue Bonds	Funding Bonds	Voted Bonds	Sinking Fund Levy (1966-67)	Rate Voted Special Voted General Fund (KRS 157.440)	Date Tax Voted	Number of Years (I. Indefinite)	Rate Voted Special Voted Building Fund (KRS 160.477)	Date Tax Voted	Number of Years (I. Indefinite)	Total Assessment (1966-67) Excluding Bank Shares	Percentage of Total Assessment to Bonds Outstanding
Ferguson	$ 70,000	$ -	$ -	$ -	$ -	-	-	$ -	-	-	$ 3,985,160	1.76%
Fort Thomas	1,210,000	-	12,000	.0057	-	-	-	-	-	-	83,647,915	1.45
Frankfort	275,000	-	-	-	-	-	-	.28	11-7-50	25	12,725,777	2.16
Fulton	68,000	-	-	-	.50	1-26-60	I.	-	-	-	16,799,487	.40
Georgetown	559,000	-	-	-	-	-	-	.05-.50	11-2-54	I.	24,751,490	2.26
Glasgow	1,873,000	-	-	-	1.00	5-28-63	I.	.50	2-24-59	I.	61,569,298	3.04
Greenup	179,000	-	-	-	-	-	-	.05-.50	7-2-55	30	7,982,615	2.24
Greenville	148,000	-	-	-	-	-	-	.05-.45	10-7-53	20	24,462,100	.61
Harlan	653,000	-	-	-	-	-	-	.05-.50	10-4-53	I.	19,928,142	3.27
Harrodsburg	498,000	-	-	-	-	-	-	.50	12-15-53	30	33,069,581	1.51
Hazard	731,000	-	122,000	6.4	-	-	-	.05-.35	11-8-60	20	32,641,400	2.24
Henderson	1,646,000	-	-	-	-	-	-	.05-.35	11-6-51	I.	68,333,877	2.41
Hopkinsville	1,732,000	-	-	-	-	-	-	.50	11-3-53	25	77,873,552	2.22
Irvine	108,000	-	-	-	-	-	-	-	-	-	10,646,658	1.01
Jackson	33,000	-	-	-	-	-	-	.50	11-3-53	20	6,160,174	.54
Jenkins	-0-	-	-	-	-	-	-	-	-	-	14,874,036	-
Leitchfield	364,000	-	-	-	.25	5-28-63	25	.05-.50	3-25-55	I.	17,770,609	2.05
Lexington	3,387,000	-	-	-	-	-	-	-	-	-	138,970,896	2.44

School District	Revenue Bonds	Funding Bonds	Voted Bonds	Sinking Fund Levy (1966-67)	Rate Voted Special Voted General Fund (KRS 157.440)	Date Tax Voted	Number of Years (I. Indefinite)	Rate Voted Special Voted Building Fund (KRS 160.477)	Date Tax Voted	Number of Years (I. Indefinite)	Total Assessment (1966-67) Excluding Bank Shares	Percentage of Total Assessment to Bonds Outstanding
Liberty	$ 106,000	$ -	$ -	$ -	$ -	-	-	$ .50	9-8-59	20	$ 10,233,680	1.04%
London	443,000	-	-	-	-	-	-	.05-.50	6-19-54	20	34,450,800	1.29
Louisville	13,297,000	-	-	-	-	-	-	.50	11-3-59	14	1,720,693,118	.77
Ludlow	353,000	-	-	-	-	-	-	.05-.45	5-8-54	I.	24,330,334	1.45
Lynch	-0-	-	-		1.50	9-16-57	I.	-	-	-	10,532,489	-
Mayfield	675,000	-	-	-	-	-	-	.05-.50	11-3-53	I.	49,412,655	1.37
Maysville	159,000	-	-	-	.38	5-29-58	I.	-	-	-	51,497,618	.31
Middlesboro	838,000	-	-	-	1.00	4-20-65	I.	-	-	-	37,992,645	2.21
Monticello	214,000	-	-	-	-	-	-	.05-.50	3-18-52	I.	12,839,322	1.67
Mt. Sterling	515,000	-	-	-	-	-	-	.05-.50	5-26-59	25	27,108,134	1.90
Murray	189,000	-	28,000	1.1	-	-	-	.25	6-16-53	I.	55,288,364	.34
Newport	1,938,500	-	-	-	-	-	-	.05-.50	11-8-55	I.	46,891,800	4.13
Owensboro	4,745,000	-	245,000	1.6	-	-	-	.50	6-24-60	I.	197,773,747	2.40
Paducah	2,535,000	-	-	-	-	-	-	.05-.50	11-6-51	25	60,752,150	4.17
Paintsville	430,000	-	-	-	.50	5-26-64	I.	.05-.30	8-20-53	I.	25,710,035	1.67
Paris	941,000	-	112,000	2.2	.50	11-6-62	I.	-	-	-	36,441,269	2.58
Pikeville	815,000	-	-	-	-	-	-	.05-.50	4-3-62	I.	41,616,357	1.96
Pineville	-0-	-	-	-	-	-	-	.05-.25	3-7-50	I.	11,126,374	-

School District	Revenue Bonds	Funding Bonds	Voted Bonds	Sinking Fund Levy (1966-67)	Rate Voted Special Voted General Fund (KRS 157.440)	Date Tax Voted	Number of Years (I. Indefinite)	Rate Voted Special Voted Building Fund (KRS 160.477)	Date Tax Voted	Number of Years (I. Indefinite)	Total Assessment (1966-67) Excluding Bank Shares	Percentage of Total Assessment to Bonds Outstanding
Providence	$ 201,000	$ -	$ -	$ -	$ -	-	-	$.05-.50	4-23-50	25	$ 10,303,255	1.95%
Raceland	636,000	-	-	-	.50	4-13-61	I.	.05-.50	6-25-55	25	18,437,180	3.45
Richmond	713,000	-	-	-	-	-	-	.05-.50	11-8-55	I.	39,186,200	1.82
Russell	1,478,000	-	-	-	.50	2-23-60	I.	.05-.50	5-18-54	20	80,909,230	1.83
Russellville	997,000	-	-	-	-	-	-	.50	11-7-50	30	29,091,716	3.43
Science Hill	9,000	-	-	-	-	-	-	-	-	-	4,282,050	.21
Scottsville	148,000	-	-	-	-	-	-	.05-.50	11-3-53	20	16,462,215	.90
Shelbyville	428,000	-	-	-	.50	11-3-64	I.	-	-	-	46,426,192	.92
Silver Grove	112,000	-	-	-	.50	6-3-63	I.	.05-.50	6-28-54	I.	5,132,788	2.18
Somerset	1,426,000	20,000	-	-	.50	2-11-63	I.	.05-.50	4-19-54	25	47,879,300	2.98
Southgate	-0-	-	-	-	-	-	-	-	-	-	10,653,200	-
Van Lear	-0-	-	-	-	-	-	-	-	-	-	1,283,890	-
Walton-Verona	334,000	-	-	-	-	-	-	.50	11-7-50	30	14,258,205	2.34
West Point	3,000	-	-	-	.50	5-26-59	I.	-	-	-	5,081,896	.06
Williamsburg	225,000	-	-	-	-	-	-	-	-	-	14,532,420	1.55
Williamstown	70,000	-	-	-	.30	5-6-66	I.	.05-.50	4-5-55	I.	19,317,650	.36

BONDS OUTSTANDING

Date	Revenue Bonds	Funding Bonds	Voted Bonds
6-30-66	$224,494,500	$316,000	$1,412,000
6-30-65	210,346,000	342,000	1,580,000
6-30-64	201,073,000	368,000	1,692,000
6-30-63	187,738,000	396,000	1,852,000
6-30-62	164,223,000	424,000	1,883,000
6-30-61	145,965,000	457,000	2,053,000
6-30-60	126,144,000	124,000	2,211,500
6-30-59	118,868,000	159,000	2,352,500
6-30-58	107,366,000	228,000	2,503,000
6-30-57	93,636,000	273,000	1,729,000

SCHOOL BUILDING REVENUE BONDS
JULY 1, 1965 THROUGH JUNE 30, 1966

AMOUNT OF BONDS SOLD DURING FISCAL YEAR 1965-66 - $26,631,000

DISTRICT	DATE SOLD	AMOUNT	RATE
Anderson County	April 1, 1966	$ 700,000	4.22%
Bell County	May 21, 1966	100,000	4.24
Boyle County	October 13, 1965	400,000	3.67
Breathitt County	June 27, 1966	400,000	4.71
Bullitt County	April 18, 1966	300,000	4.15
Caldwell County	February 22, 1966	110,000	4.08
Fayette County	October 19, 1965	2,640,000	3.77
Fayette County	February 15, 1966	1,560,000	4.05
Harlan County*	September 8, 1965	492,000	3.73
Jefferson County	March 1, 1966	3,400,000	4.36
Jefferson County	May 17, 1966	1,170,000	4.13
Jefferson County	December 16, 1965	3,250,000	4.06
Kenton County	June 16, 1966	615,000	4.32
Livingston County	September 7, 1965	180,000	3.63
Marion County	March 19, 1966	100,000	4.28
Marshall County	April 19, 1966	192,000	4.15
Mason County	December 23, 1965	54,000	3.84
McCracken County	September 23, 1965	1,000,000	3.72
Monroe County	November 30, 1965	600,000	3.98
Muhlenberg County	October 21, 1965	170,000	3.85
Spencer County	January 25, 1966	100,000	3.92
Union County	March 22, 1966	480,000	4.28
Bellevue Independent	July 14, 1965	540,000	3.85
Burgin Independent	January 4, 1966	63,000	4.07
Cloverport Independent**	November 15, 1965	130,000	3.91
Covington Independent	June 2, 1966	1,450,000	4.41
East Bernstadt Independent	August 5, 1965	75,000	3.91
Elizabethtown Independent	December 6, 1965	240,000	4.14
Lexington Independent	August 5, 1965	700,000	3.55
Louisville Independent	June 14, 1966	4,000,000	4.12
Owensboro Independent	April 12, 1966	900,000	4.16
Paducah Independent	June 14, 1966	200,000	4.06
Russellville Independent	June 28, 1966	150,000	4.34
Williamsburg Independent	May 4, 1966	170,000	4.24

* Refunding Bond Issue, included in grand total

** $87,000 of this issue is refunding bonds, included in grand total

District	School	Grades Housed	Student Capacity	Regular Classrooms	Special Classrooms	Adm. Offices	Library	Cafeteria	Multipurpose	Kitchen	Auditorium	Gymnasium	Shower & Locker	Health	Guidance	
Middlesboro Ind.	Middlesboro H. S.	9-12	1000	27	12	x	x	x		x		x	x	x	x	
Anderson County	Anderson Co. H. S.	10-12	450	14	7	x	x		x	x			x	x	x	
Simpson County	Simpson Co. H. S.	9-12	810	23	4	x	x	x		x			x	x	x	
Fort Knox Dep.	McDonald Jr. H. S.	7-9	600	22	7	x	x	x		x		x	x	x	x	
Hardin County	North Hardin	7-8	600	20		x	x		x	x						
Fayette County	Southern Jr. H. S.	7-9	1230	21	20	x	x	x		x		x	x			
Jefferson Co.	Shipley Lane	6-8	950	20	7	x	x	x	x	x			x	x	x	
Fayette County	Dixie Elem.	1-6	750	24	2	x	x		x	x				x	x	
Fayette County	Lansdowne Elem.	1-6	750	25	1	x	x		x	x				x	x	
Jefferson Co.	Lower Hunters Trace	1-6	720	24	2	x	x	x		x			x	x		
Pike County	Greasy Creek	1-8	300	10		x	x		x	x				x		
Breathitt Co.	Breathitt Co. Elem.	1-8	1100	16	4	x	x		x	x						
Jefferson Co.	Bluelick Road	1-6	750	22	2	x	x		x	x			x	x	x	
Monroe County	Rock Bridge Elem.	1-8	240	8		x	x		x	x				x		
Knott County	Emmalena Elem.	1-8	300	10	1	x	x		x	x				x		
Pike County	Brushy Creek	1-8	300	10			x		x	x				x		

District	School	Capacity	Grades Housed	Date of Contract	Contract	Total Square Ft.	Cost per Square Ft.	Cost per Pupil
Middlesboro, Ind.	Middlesboro H.S.	1000	9-12	8-66	$1,669,273.00	104,180	$16.02	$1669.27
Anderson County	Anderson Co. H.S.	610	10-12	1-66	838,318.00	62,454	13.42	1374.30
Simpson County	Simpson Co. H.S.	650	7-12	6-66	703,665.00	56,700	12.41	1082.56
Fort Knox Dep.	McDowell Jr.	960	7-9	10-66	$1,163,000.00	64,547	$18.02	$1211.45
Hardin County	North Hardin	600	7-8	4-66	598,445.00	37,779	15.76	997.40
Fayette County	Southern Jr.	1230	7-9	8-66	1,108,000.00	80,500	13.76	900.81
Jefferson County	Shipley Lane	750	7-9	11-65	1,054,890.00	79,000	13.53	1455.00
Fayette County	Dixie Elem.	780	1-6	12-65	$ 577,836.00	44,343	$13.03	$ 740.81
Fayette County	Lansdowne Elem.	780	1-6	12-65	582,133.75	44,528	13.07	746.32
Jefferson County	Lower Hunters Trace	750	1-6	3-66	768,570.00	44,012	17.46	1024.76
Pike County	Greasy Creek	300	1-8	7-66	284,055.00	17,200	16.51	946.83
Breathitt County	Breathitt Co. Elem.	600	1-6	6-66	641,229.00	43,992	14.80	1068.70
Jefferson County	Bluelick Road	600	1-6	12-65	717,109.47	45,720	15.68	1195.18
Monroe County	Rock Bridge Elem.	240	1-8	10-66	266,740.00	17,050	15.64	1111.42
Knott County	Emmalena Elem.	300	1-6	10-66	338,630.00	21,960	15.42	1128.77
Pike County	Brushy Creek	300	1-8	6-66	291,500.00	17,078	17.05	971.66

District	School	No. of Instructional Areas	Sq. Ft.	Contract	Date of Contract	Cost per Unit	Cost per Sq. Ft.
Garrard County	Vocational Extension School	7	21,600	$283,750.00	9-66	$1970.49	$13.14
Marion County	Area Vocational Extension	10	24,890	348,050.00	2-66	1392.20	13.98
Martin County	Vocational Extension School	9	22,175	350,000.00	11-66	1620.37	15.78
Pike County	Belfry Vocational School	7	21,200	314,800.00	10-66	1874.00	14.85

Vocational Schools

ELEMENTARY
SCHOOLS

CAMPBELL COUNTY SCHOOL DISTRICT

GRANDVIEW ELEMENTARY SCHOOL

GENERAL DESCRIPTION:

Size of Site	3 Acres
Water and Sewage	City services available to property line.
Grades Housed	1 Through 6
Student Capacity	720
Type Heat	Circulated hot-water heating system gas-fired hot-water boiler
Extent and Type of Cooling	None
Area in Square Feet	39,890*
Construction Cost Per Sq. Ft.	$13.40 (AIA Computation)
Total Construction Cost	$502,386
Architects	Kral, Zepf, Freitag & Associates, Cincinnati, Ohio
Engineers	Same as above
General Contractor	Robert T. Klensch, Inc.
Date Construction Contract	June 1965
Date Completed	August 1966

Special Features - 18 classrooms with additional facilities for Library, Administrative Offices, Teachers Work Room and Conference Room, Teachers Lounge, Health Room, Multi-purpose Room, Kitchen and Covered Play Area.

*Including 56 Ft. x 92 Ft. covered play area.


GRANDVIEW ELEMENTARY SCHOOL
BELLEVUE, KENTUCKY
KRAL, ZEPF, FREITAG & ASSOCIATES
ENGINEERS & ARCHITECTS


GRANDVIEW AVE.
WASHINGTON AVE.
LOCUST ST.
WARD AVE.
LINCOLN AVE.
FOOTE AVE.
PARKING
CLASSROOM BUILDING
LOADING DOCK
MULTI-PURPOSE BUILDING
PARKING
580
575
570
560
NORTH
0
25
50
75
100

PLOT PLAN

GRANDVIEW ELEMENTARY SCHOOL
BELLEVUE, KENTUCKY

KRAL, ZEPF, FREITAG & ASSOCIATES
ARCHITECTS & ENGINEERS
CINCINNATI, OHIO


LOADING DOCK
DRY GROCERY STORAGE RM.
KITCHEN
MECH. EQUIP. RM.
GIRLS
BOYS
CORRIDOR
CORRIDOR
STAGE
FACULTY LOUNGE
STOR.
STORAGE
FIRST AID RM.
UNEXCAVATED
GYMNASIUM
north
0 5 10 15 20

LOWER LEVEL & MULTIPURPOSE LEVEL

GRANDVIEW ELEMENTARY SCHOOL
BELLEVUE, KENTUCKY

KRAL, ZEPF, FREITAG & ASSOCIATES
ARCHITECTS & ENGINEERS
CINCINNATI, OHIO


CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM
GIRLS
BOYS
ROOF LEVEL
KITCHEN BELOW
CORRIDOR
CORRIDOR
CORRIDOR
STAGE
WORK AND STORAGE
CORRIDOR
WAITING ROOM
PRINCIPAL'S OFFICE
CONFERENCE RM
CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM
GYMNASIUM
NORTH

FIRST FLOOR CLASSROOMS & OFFICES

GRANDVIEW ELEMENTARY SCHOOL
BELLEVUE, KENTUCKY

KRAL, ZEPF, FREITAG & ASSOCIATES
ARCHITECTS & ENGINEERS
CINCINNATI, OHIO


ROOF LEVEL
BOYS
GIRLS
CLASSROOM
CORRIDOR
WORK ROOM
CONF ROOM
CLASSROOM
CLASSROOM
LIBRARY
CLASSROOM
CLASSROOM
CORRIDOR
CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM
NORTH

SECOND FLOOR CLASSROOMS & LIBRARY

GRANDVIEW ELEMENTARY SCHOOL
BELLEVUE, KENTUCKY

KRAL, ZEPF, FREITAG & ASSOCIATES
ARCHITECTS & ENGINEERS
CINCINNATI, OHIO

BOONE COUNTY SCHOOL DISTRICT

A. M. YEALEY ELEMENTARY SCHOOL

GENERAL DESCRIPTION:

Size of Site	10 Acres (approximately)
Water and Sewage	City services available to property line
Grades Housed	1 Through 6
Student Capacity	600
Type Heat	Hot water (gas fired)
Extent and Type of Cooling	Rough-in Future A/C
Area in Square Feet	26,250
Construction Cost Per Sq. Ft.	$15.50
Total Construction Cost	$407,229.63*
Architects	Fisk, Rinehart & Hall, McAllister, Stockwell
Engineers	Same as above
General Contractor	Robert T. Klensch, Inc.
Date Construction Contract	January 17, 1963
Date Completed	September 1963

*Cost figure includes Kitchen Equipment and Locker, but excludes Library, Shop, Home Economic and Laboratory Furnishings, Land Cost and Fees.




PLAYGROUND
NORTH

SITE PLAN

A.M. YEALEY SCHOOL

FLORENCE KENTUCKY

FISK—RINEHART
&
HALL—McALLISTER—STOCKWELL
Architects Engineers
Cincinnati,Ohio—Covington,Kentucky

A.M. YEALEY SCHOOL

FLORENCE , KENTUCKY

FISK — RINEHART
&
HALL—McALLISTER—STOCKWELL
Architects Engineers
Cincinnati, Ohio — Covington, Kentucky


C
LIB.
W.R.
G
B
JWR.
M.E.
F.A.
K.S.
O
E.L.
T.L.
S
K
ST.
M.P.R.
C—CLASSROOM
LIB.—LIBRARY
W.R.—WORK ROOM
G—GIRL'S TOILET
B—BOY'S TOILET
JWR.—JANITOR WORK ROOM
M.E.—MECHANICAL EQUIPMENT
F.A.—FIRST AID ROOM
K.S.—KITCHEN STORAGE
O—OFFICE
K—KITCHEN
T.L.—TEACHER'S LOUNGE
ST.—STORAGE
S—SCULLERY
E.L.—ENTRANCE LOBBY
M.P.R.—MULTI-PURPOSE ROOM

FLOOR PLAN

FAYETTE COUNTY SCHOOL DISTRICT

LANSDOWNE ELEMENTARY SCHOOL

GENERAL DESCRIPTION:

Size of Site	9 Acres
Water and Sewage	Provided by city
Grades Housed	1 Through 6 (non-graded)
Student Capacity	750
Type Heat	Seven roof top multi-zone units
Extent and Type of Cooling	Air handling equipment for 50,000 CFM air-conditioning system.
Area in Square Feet	45,000
Construction Cost Per Sq. Ft.	$12.89
Total Construction Cost	$580,000
Architects	Chrisman & Miller, Lexington, Kentucky
Engineers	Hugh Dillehay & Associates, Lexington, Kentucky
General Contractor	Contractors Lumber & Supply Co., Lexington, Kentucky
Date Construction Contract	Construction started January 1966
Date Completed	October 1966

Special Features - Rectangular 184' x 242' school, designed for compactness, ease of maintenance, and minimum heating and cooling costs. The building contains six - 80' x 48' multi-classrooms, each serving four non-graded learning groups with team teachers. Floors carpeted for controlled accoustics in large area. Resource center carpeted with study carrels for individual research. (Full time librarian) Multi-purpose and service area 3' below other floors, with music room doubling as stage. Large teacher's work area and lounge with individual cabinets, work top, and shelves for each teacher. Minimum window area for maximum control of heat, cooling, and light. This school, as other schools in Fayette County, is located adjacent to a city park to provide additional play area for the students, and eliminate the need for buying excessive acreage of land.


SERVICE DRIVE
SERVICE COURT
PLAY AREA

SITE PLAN

LANSDOWNE ELEMENTARY SCHOOL

FAYETTE COUNTY KENTUCKY

scale 0 40 80

CHRISMAN · MILLER · ARCHITECTS


MULTI-CLASSROOM
MULTI-CLASSROOM
MULTI-CLASSROOM
CORRIDOR
FOOD STORAGE
STOR.
MULTI-PURPOSE
STORAGE
MECH.
SPECIAL E.D.
CORRIDOR
MULTI-CLASSROOM
MULTI-CLASSROOM
MULTI-CLASSROOM
BUS LOADING

FLOOR PLAN

LANSDOWNE ELEMENTARY SCHOOL

FAYETTE COUNTY KENTUCKY

scale 0 25 50

chrisman • miller • architects

FRANKLIN COUNTY SCHOOL DISTRICT

ELKHORN ELEMENTARY

GENERAL DESCRIPTION:

Size of Site	24 Acres (including Junior High site)
Water and Sewage	Available from county
Grades Housed	1 Through 6
Student Capacity	655 (There are no provisions for expansion for this building due to the limited size of this site which houses this elementary plus a Junior High of 1,152 students.)
Type Heat	Forced hot air
Extent and Type of Cooling	Music room and offices air-conditioned with provisions for future classroom unit air-conditioning.
Area in Square Feet	47,000
Construction Cost Per Sq. Ft.	$16.20 (Estimated)
Total Construction Cost	$746,000 (Estimated)
Architects	Sullivan, Issacs and Sullivan, Frankfort, Kentucky
Engineers	Maxfield and Edwards, Covington, Kentucky
General Contractor	Fain & Johnston, Inc., Lexington, Kentucky
Date Construction Contract	Construction started September 1, 1966
Date Completed	September 1, 1967 (Estimated)

Special Features - To construct a quality building at a reasonable cost resulted in a building in the shape of a cube, reducing outside wall area that is expensive to construct and costly to maintain.

The hillside site requires a two level plan designed to fit the site.

The building will be constructed utilizing masonry bearing walls supporting steel bar joist, built-up roof and acoustical tile ceilings. Exterior walls will be of maintenance free, brick, aluminum and glass with interior walls of concrete block painted. All corridor, toilet and kitchen walls to be epoxy tile like finish and epoxy wainscot in classroom areas.

Floor finish to be terrazzo in all entrance areas, toilets and kitchen, vinyl asbestos tile in corridors and cafeteria and asphalt tile in remainder of buildings.




745
740
740
745
750
755
765
770
770
US 60 TO GEORGETOWN
777
780
785
EXIST. TENNIS COURTS
EXIST. BASEBALL FIELD
PARKING
NEW ELKHORN ELEMENTARY SCHOOL
ELKHORN JR. HIGH SCHOOL
BOARD OF EDUCATION OFFICE
US 60 TO LEXINGTON
ROADSIDE PARK
745
740
735
730
730
735
740
THORNHILL - EAST FRANKFORT BY-PASS
745
750
755
760
770
775
780
785
0 50 100 200 300
NORTH

PLOT PLAN

NEW ELKHORN ELEMENTARY SCHOOL
FRANKFORT, FRANKLIN COUNTY, KENTUCKY


BOILER RM.
JAN. & STOR.
CR.
CR.
CR.
STR.
CR.
CR.
UNEXCAVATED
CORRIDOR
J.C.S.
B.T.
G.T.
VEST.
WAIT.
GEN. OFF.
REC.
BK. ST.
CLO.
CORRIDOR
PRIN. OFF.
OFF.
FACUL.
M.
W.
T.
CLINIC
WK. RM.
STOR.
LIBRARY.
CR.
CR.
CR.
0 10 20 30 40 50
NORTH

GROUND FLOOR PLAN

NEW ELKHORN ELEMENTARY SCHOOL
FRANKFORT, FRANKLIN COUNTY, KENTUCKY


CR.
CR.
CR.
CR.
CR.
OFF.
MUSIC RM.
PASSAGE
DR.
STAGE
STOR.
CR.
CR.
SH. DRY.
T.
BOYS LK. RM.
SH.
DRY.
T.
ALL PURPOSE RM.
CORRIDOR
JAN.
G.T.
B.T.
J.S.LK.
STORAGE
GIRLS LK. RM.
CR.
KITCHEN
CAFETERIA
CR.
D.W.
T.
STOR
CR.
CR.
CR.
CR.
CR.
NORTH
0
10
20
30
40
50

FIRST FLOOR PLAN

NEW ELKHORN ELEMENTARY SCHOOL
FRANKFORT, FRANKLIN COUNTY, KENTUCKY

FRANKLIN COUNTY SCHOOL DISTRICT

COLLINS LANE ELEMENTARY

GENERAL DESCRIPTION:

Size of Site	16 Acres
Water and Sewage	Available from county
Grades Housed	1 Through 6
Student Capacity	630 (The building has been designed to be expanded to 840.)
Type Heat	Forced hot air
Extent and Type of Cooling	Music room and offices air-conditioned with provisions for future classroom unit air-conditioning.
Area in Square Feet	44,465
Construction Cost Per Sq. Ft.	$16.20 (Estimated)
Total Construction Cost	$721,000 (Estimated)
Architects	Sullivan, Issacs and Sullivan, Frankfort, Kentucky
Engineers	Maxfield and Edwards, Covington, Kentucky
General Contractor	Fain & Johnston, Inc., Lexington, Kentucky
Date Construction Contract	Construction started September 1, 1966
Date Completed	September 1, 1967 (Estimated)

Special Features - To construct a quality building at a reasonable cost resulted in a building in the shape of a cube, reducing outside wall area that is expensive to construct and costly to maintain.

The hillside site requires a two level plan designed to fit the site.

The building will be constructed utilizing masonry bearing walls supporting steel bar joist, built-up door and acoustical tile ceilings. Exterior walls will be of maintenance free, brick, aluminum and glass with interior walls of concrete block painted. All corridor, toilet and kitchen walls to be epoxy tile like finish and epoxy wainscot in classroom areas.

Floor finish to be terrazzo in all entrance areas, toilets and kitchen. Vinyl asbestos tile in corridors and cafeteria and asphalt tile in remainder of buildings.




SOFTBALL FIELDS
PLAY AREA
PARKING
COLLINS LANE
LENWOOD AV.
CROSS HILL DR.
730
735
740
745
750
755
760
765
770
775
778
780
0 50 100 200 300
NORTH

PLOT PLAN

NEW COLLINS LANE ELEMENTARY SCHOOL
FRANKFORT, FRANKLIN COUNTY, KENTUCKY


NEW COLLINS LANE ELEMENTARY SCHOOL
FRANKFORT, FRANKLIN COUNTY, KENTUCKY
LOWER LEVEL PLAN
UNEXCAVATED
CORRIDOR
C.R.
C.R.
C.R.
C.R.
C.R.
C.R.
C.R.
ST
ST
STOR
FUTURE EXP
NORTH
0
10
20
30
40
50


C.R.
C.R.
C.R.
C.R.
C.R.
C.R.
C.R.
FUTURE EXP.
CORRIDOR
PRIN. OFF.
STOR.
REC.
OFFICE
ENTRY
OFF.
T.
T.
CONFER.
FACUL.
REST RM.
T.
CLINIC
B.T.
B.T.
OFF
MUSIC RM.
J. CLOS.
DRESS RM.
STAGE
STOR.
LA. RM.
DRY
BOYS
SH.
LA. RM.
SH.
GIRLS
DRY
DRY STOR.
KITCHEN
MULTI - PURPOSE
CAFETERIA
JANITOR STOR.
BOILER RM.
B.T.
G.T.
REC.
RM.
STOR.
LIBRARY
CORRIDOR
C.R.
C.R.
C.R.
C.R.
C.R.
C.R.
C.R.
FUTURE EXP.

FIRST FLOOR PLAN

0 10 20 30 40 50
NORTH

NEW COLLINS LANE ELEMENTARY SCHOOL
FRANKFORT, FRANKLIN COUNTY, KENTUCKY

GREEN COUNTY SCHOOL DISTRICT

PIERCE ELEMENTARY SCHOOL

GENERAL DESCRIPTION:

Size of Site	8 Acres
Water and Sewage	Automatic pump from well, septic tank
Grades Housed	1 Through 8
Student Capacity	240 (future addition may be added to east end of building)
Type Heat	Coal fired - hot water
Extent and Type of Cooling	None
Area in Square Feet	14,388
Construction Cost Per Sq. Ft.	$10.91
TotalConstruction Cost	$186,000.00
Architects	Thomas J. Nolan & Sons, Louisville, Kentucky
Engineers	Same as above
General Contractor	Ernest Simpson Construction Company, Glasgow, Kentucky
Date Construction Contract	May 31, 1962
Date Completed	February 9, 1963



PIERCE ELEMENTARY SCHOOL **Thomas J Nolan and Sons · Architects**


N
[illegible] ELEMENTARY SCHOOL
STATE HIGHWAY 2.8


STORAGE
KITCHEN
DISH WASH
ALL PURPOSE ROOM
CLASS ROOM
ENTRY
TEACHERS ROOM
FIRST AID
BOYS
GIRLS
FUEL RM
BOOK RM
BOILER RM
CLASS ROOM
CLASS ROOM
CORRIDOR
CLASS ROOM
CLASS ROOM
CLASS ROOM
ENTRY
GENERAL OFFICE
PRINCIPAL
CLASS ROOM
CLASS ROOM

PIERCE ELEMENTARY SCHOOL
GREEN COUNTY BOARD OF EDUCATION
THOMAS J. NOLAN and SONS • ARCHITECTS

JOHNSON COUNTY SCHOOL DISTRICT

W. R. CASTLE ELEMENTARY SCHOOL

GENERAL DESCRIPTION:

Size of Site	6½ Acres
Water and Sewage	Water provided from well. A septic tank provides for sewage disposal.
Grades Housed	1 Through 9
Student Capacity	480
Type Heat	Hot water
Extent and Type of Cooling	None
Area in Square Feet	26,000
Construction Cost Per Sq. Ft.	$11.64
Total Construction Cost	$302,699.25
Architects	M. Gibson Taylor, Jr.
Engineers	Hugh Dillehay & Assoc., Lexington, Kentucky
General Contractor	Preston Building & Supply Co., Inc., Paintsville, Kentucky
Date Construction Contract	October 1962
Date Completed	January 1964


N 24° 15' W 185'
S 21° 00' W 320'
N
N 14° 15' W 144'
S 30° 00' W 50'
N 30° 00' W 114'
S 41° 30' W 64'
S 45° 00' W 55'
N 4° 30' E 48'
S 49° 00' W 55'
SCHOOL
N 38° 00' W 130'
S 47° 30' W 78'
S 37° 30' W 86'
S 59° 30' W 256'
US 23
S 56° 30' E 139'
TOM'S CREEK
WHITTENDVILLE BRANCH
DUE EAST 95'
S 79° 00' E 110'

SITE PLAN

W. R. CASTLE ELEMENTARY SCHOOL

SCALE - 1" = 200'



FIRST FLOOR PLAN
W. R. CASTLE ELEM. SCHOOL
SCALE-1" = 40'

1. Class Room
2. Toilet
3. Janitor's Storage
4. Storage
5. Lounge
6. Office
7. Lobby
8. Corridor
9. Stairwell
10. Multipurpose Room
11. Dressing Rooms
12. Stage
13. Food Storage
14. Freezer Space
15. Kitchen
16. Coal Bin
17. Boiler Room

STATE OF KENTUCKY
M. GIBSON
TAYLOR, JR.
378
REGISTERED
ARCHITECT



1. Class Room
2. Toilet
3. Janitor's Storage
8. Corridor
9. Stairwell
10. Multipurpose Room Upper Part
18. Library

SECOND FLOOR PLAN
W. R. CASTLE ELEM. SCHOOL
SCALE - 1" = 40'

STATE OF KENTUCKY
M. GIBSON
TAYLOR, JR.
378
REGISTERED
ARCHITECT

KNOTT COUNTY SCHOOL DISTRICT

HINDMAN ELEMENTARY SCHOOL

GENERAL DESCRIPTION:

Size of Site	6 Acres
Water and Sewage	Water provided from well. Disposal plant necessary
Grades Housed	1 Through 9
Student Capacity	350
Type Heat	Hot water
Extent and Type of Cooling	None
Area in Square Feet	34,274.5
Construction Cost Per Sq. Ft.	$9.00
Total Construction Cost	$308,470.00
Architect	M. Gibson Taylor, Jr.
Engineer	M. Gibson Taylor, Jr., Winchester, Kentucky
General Contractor	Big Sandy & Ohio Valley Construction Company, Meally, Kentucky
Date Construction Contract	February 1958
Date Completed	December 1959


S 44°34'E 117'
S23°18'E 158'
S10°35'E 157'
S66°20'E 135'
S66°22'E85'
N
S15°16'E 157'
S16°00'E 153'
S33°30'E 130'
N54°53'E 115'
S64°40' W 25'
N50° 25'W 122'
N57°10'W 150'
N76°39' E 89'
N51°00'W 150'
N32° 54' W 543'
N38° 30' W 104'
US 80

SITE PLAN
HINDMAN ELEMENTARY SCHOOL
SCALE-1"=200'


230'- 2"
143'- 2"
9
10
9
17
4
16
14
8
15
4
7
1
6
6
3
5
3
5
4
11
13
12
4
2
3
4

FLOOR PLAN HINDMAN ELEMENTARY SCHOOL

SCALE 1' = 40'

1. Lobby
2. Class Room
3. Toilet
4. Storage
5. Teachers Lounge
6. Office
7. Book Store
8. Multipurpose Room
9. Dressing Room
10. Stage
11. Girls Toilet
12. Boys Toilet
13. Mechanical Room
14. Kitchen
15. Dishwashing
16. Cooler
17. Garbage Room

STATE OF KENTUCKY
M. GIBSON
TAYLOR, JR.
378
REGISTERED
ARCHITECT

LOUISVILLE INDEPENDENT SCHOOL DISTRICT

MARGARET MERKER SCHOOL

GENERAL DESCRIPTION:

Size of Site	3 Acres
Water and Sewage	Municipal supply - Public sewer
Grades Housed	1 Through 8
Student Capacity	1,050
Type Heat	Gas fired - hot water
Extent and Type of Cooling	Completely cooled - chilled water
Area in Square Feet	69,370
Construction Cost Per Sq. Ft.	$15.03
Total Construction Cost	$1,057,839.19
Architects	Thomas J. Nolan & Sons, Louisville, Kentucky
Engineers	E. R. Ronald & Associates, Louisville, Kentucky
General Contractor	F. W. Owens & Associates, Louisville, Kentucky
Date Construction Contract	August 4, 1965
Date Completed	August 1, 1966

Special Features - This school is in part of an industrial area as well as the stock yards serving the City of Louisville. There is a bare minimum of windows in this structure and the building is completely air-conditioned. This was not planned as a luxury item but rather due to odors and noises in the neighborhood.



MARGARET MERKER ELEMENTARY SCHOOL
THOMAS J. NOLAN AND SONS
ARCHITECTS


MAIN STREET
MARGARET MERKER ELEMENTARY SCHOOL
PLAYGROUND
LINE OF OLD SCHOOL
WENZEL STREET
MARKET STREET
ALLEY
371'0"
204'0"
204'0"
360'6"
204'0"
204'0"


PRINCIPALS OFFICE
CONFERENCE ROOM
HEALTH ROOM
WAITING
VAULT
ENTRANCE LOBBY
STAIR Nº 1
CLASSROOM
CLASSROOM
CLASSROOM
STAIR Nº 2
CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM
CORRIDOR
JAN
WORK RM
TEACHERS LOUNGE
MECH EQUIP RM
STAGE STORAGE
BOYS TOILET
GIRLS TOILET
CAFETERIA AUDITORIUM
CORRIDOR
STAIR Nº 4
KITCHEN
STORE
FRIDGE
RECEIVING
CUSTODIAN
STAIR Nº 3
LOCKER ROOM
LOCKER ROOM
CAN WASH
MECHANICAL ROOM

MARGARET MERKER ELEMENTARY SCHOOL 1st FLOOR
THOMAS J NOLAN and SONS • Architects


CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM
MATERIALS CENTRE
AUDIO VISUAL STORAGE
STAIR Nº 1
LIBRARY
STAIR Nº 4
CLASSROOM
CLASSROOM
PHYSICAL EDUCATION ROOM
CHAIR STORE
ART PROJECT ROOM
TEACHER'S LOUNGE
GIRLS
BOYS
CLASSROOM
CLASSROOM
STAIR Nº 2
CLASSROOM
STAIR Nº 3
CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM
CLASSROOM

MARGARET MERKER ELEMENTARY SCHOOL · SECOND FLOOR
THOMAS J NOLAN and SONS · Architects

MARION COUNTY SCHOOL DISTRICT

CALVARY ELEMENTARY SCHOOL

GENERAL DESCRIPTION:

Size of Site	35 Acres
Water and Sewage	Water available and sewage disposed of through an absorption field.
Grades Housed	1 Through 8
Student Capacity	240
Type Heat	Forced hot air
Extent and Type of Cooling	Provisions for future air-conditioning
Area in Square Feet	21,086
Construction Cost Per Sq. Ft.	$13.40
Total Construction Cost	$283,000
Architects	Gray and Coblin, Architects
Engineers	Leggett & Irvan, Structural Engineers E. W. Neel Associates, Mechanical Engineers
General Contractor	Ernest Simpson Construction Company
Date Construction Contract	Construction started in March 1965
Date Completed	Occupied in October 1965

Special Features - All Classrooms are grouped around the Library. All-weather play areas are adjacent to lower grade classrooms. A folding partition allows stage to be used as a music room or classroom.


FOOTBALL FIELD
POND
BASEBALL DIAMOND
EXIST. FENCE
EXIST. FENCE TO BE REMOVED
EXISTING BARN & SILO TO BE REMOVED
PLAY AREA 3RD - 8TH GRADES
FUTURE EXPANSION
PLAY AREA 1ST & 2ND GRADES
WATER PIPE
GAS PIPE
ADJACENT PROPERTY
ALTERNATE LOCATION FOR SERVICE TO CHURCH
RECOMMENDED LOCATION FOR SERVICE TO CHURCH
EXISTING CHURCH
METER
TO LEBANON
FIRE HYDRANT
TRANS. POLE
SEPTIC TANK
TEACHERS PARKING
HOUSE SEWER
ABSORPTION FIELD
BUS DELIVERY
OVERHEAD ELECTRIC SERVICE (W/ TELEPHONE)
NORTH

SITE PLAN
SCALE: 1" = 100'-0"

Calvary Elementary School Marion County Kentucky Gray and Coblin Archs.


FUTURE EXPANSION
COVERED PLAY AREA
FIFTH 27'×30'
SIXTH 27'×30'
EIGHTH 27'×30'
SECOND 27'×32'
TOIL.
TOIL.
ENTRY
JANITOR
ENTRY
GIRLS 15'×15'
WORK 10'×11'
BOYS 15'×15'
STOR. 10'×11'
LIBRARY 25'×30'
SEVENTH 27'×30'
OFFICE
OFFICE
SERVICE ENTRANCE
FIRST 27'×32'
MECHANICAL 23'×23'
KITCHEN 30'×24'
TOIL.
GARBAGE
REFR.
D.W.
DRY STOR. 17'×17'
SERVING
COVERED PLAY AREA
THIRD 27'×30'
FOURTH 27'×30'
STAGE 18'×36'
STOR. 7'×18'
MULT PURPOSE 59'×51'
BUS SHELTER
FLOOR PLAN 1/16" = 1'

Calvary Elementary School

McCRACKEN COUNTY SCHOOL DISTRICT

LONE OAK UPPER ELEMENTARY

GENERAL DESCRIPTION:

Size of Site	4¼ Acres
Water and Sewage	Public facilities available
Grades Housed	7 And 8
Student Capacity	515
Type Heat	Gas-fired - individual units
Extent and Type of Cooling	None
Area in Square Feet	44,200 (including 1,800 in covered walkways)
Construction Cost Per Sq. Ft.	$15.33 Enclosed area 2.75 Walkways
Total Construction Cost	$649,900
Architects	Lee Potter Smith & Associates of Paducah, Inc., Paducah, Kentucky
Engineers	Edward T. Hannan & Associates
General Contractor	Ray Black and Son, Paducah, Kentucky
Date Construction Contract	Construction started September 1965
Date Completed	September 1966

Special Features - The topography and dimensions of the site were responsible to a great degree, for the final design solution which is based around closely related functional elements situated at different levels. This approach plus the use of interior courts help create unusually exciting spaces and forms as well as providing a way to allow for future expansion without altering the circulation pattern. The various forms of the building are visually tied together by the use of a broad fascia composed of exposed black aggregate panels contrasting with the light buff brick.



SECTION A-A



ELEVATION - WEST



ELEVATION - SOUTH



SITE PLAN

[illegible]
UPPER ELEMENTARY SCHOOL
[illegible] COUNTY, KENTUCKY



PLAN



TYPICAL CLASSROOM
DOOR AND WINDOW

GENERAL METHODS OF PLUMBING, HEATING, VENTILATING AND LIGHTING

PLUMBING
[illegible]

HEATING AND VENTILATING
[illegible]

LIGHTING
[illegible]

LONE OAK
UPPER ELEMENTARY SCHOOL
McCRACKEN COUNTY, KENTUCKY

MEADE COUNTY SCHOOL DISTRICT

MULDRAUGH ELEMENTARY SCHOOL

GENERAL DESCRIPTION:

Size of Site	7 Acres
Water and Sewage	Municipal supply - Public sewer
Grades Housed	1 Through 8
Student Capacity	360 (future addition may be added to south end of building)
Type Heat	Gas fired - hot water
Extent and Type of Cooling	None
Area in Square Feet	18,900
Construction Cost Per Sq. Ft.	$12.25
Total Construction Cost	$231,767.06
Architects	Thomas J. Nolan & Sons, Louisville, Kentucky
Engineers	Same as above
General Contractor	Platoff Construction Co., Louisville, Ky.
Date Construction Contract	April 30, 1962
Date Completed	January 3, 1963



MULDRAUGH ELEMENTARY SCHOOL Thomas J Nolan and Sons · Architects


ALLEY
305.0
MULDRAUGH ELEMENTARY SCHOOL
DRIVE
N
345.0'
WENDELL AVENUE
255.2'
US 31 W & US 60

MULDRAUGH ELEMENTARY SCHOOL
MEADE COUNTY BOARD OF EDUCATION
THOMAS J. NOLAN and SONS • Architects


MULDRAUGH ELEMENTARY SCHOOL
MEADE COUNTY BOARD OF EDUCATION
THOMAS J NOLAN and SONS • ARCHITECTS
CLASS ROOM
CLASS ROOM
CLASS ROOM
LIBRARY
WORK RM
FIRST AID
CORRIDOR
CLASSROOM
BOILER
BOYS
GIRLS
KIT STORE
KITCHEN
ALL PURPOSE ROOM
CLASS ROOM
CLASS ROOM
CLASS ROOM
CLASS ROOM
CLASS ROOM
ENTRY
BOOKS
OFFICE
CLASS ROOM
CLASSROOM
CLASS ROOM

MENIFEE COUNTY SCHOOL DISTRICT

BOTTS ELEMENTARY SCHOOL

GENERAL DESCRIPTION:

Size of Site	11 Acres
Water and Sewage	Water - low capacity well and filtered rainwater in a cistern Sewage - sewage disposal plant was necessary.
Grades Housed	1 Through 6
Student Capacity	360 (expansion can be made in either direction of main wing)
Type Heat	Gas-fired hot-water boiler and classroom unit ventilators.
Extent and Type of Cooling	None
Area in Square Feet	22,551
Construction Cost Per Sq. Ft.	$11.47 (including all site work and kitchen and built-in equipment)
Total Construction Cost	$258,202
Architects	Luckett & Farley, Inc., Architects Louisville, Kentucky
Engineers	E. R. Ronald & Associates
General Contractor	Babbage Construction Company
Date Construction Contract	April 23, 1964
Date Completed	August 1965

Special Features - This building replaced the last of the one and two-room schools in mountainous Menifee County. The building was designed in strict adherence to a properly developed education program and a limited budget. The site restrictions of a creek on one side and a steep hill on the other were overcome by proper planning and site development.


BOTTS ELEMENTARY SCHOOL MENIFEE COUNTY KENTUCKY
BOARD OF EDUCATION
MISS GEORGE ALICE MOTLEY, SUPERINTENDENT
MR. NOAH PATRIKA CHAIRMAN
MR. ED BARFIELD VICE-CHAIRMAN
MR. EMERSON FERRELL MEMBER
MR. JAMES OSBORN MEMBER
MR. TUNNEY AMBURGEY MEMBER
FISCAL COURT
MR. EARL WELLS JUDGE
MR. WARREN WILLIAMS MEMBER
MR. ACEY ROBINSON MEMBER
MR. NOAH DOWNING MEMBER
MR. ISHMAEL COLLINSWORTH MEMBER
MEMBER
LUCKETT & FARLEY INC.
ARCHITECTS
LOUISVILLE, KENTUCKY


N
CREEK
PROPERTY LINE

Site Plan

BOTTS ELEMENTARY SCHOOL
MENIFEE CO KENTUCKY
SITE PLAN

25
50
100
150

LUCKETT & FARLEY
INCORPORATED
ARCHITECTS
900 WASHINGTON BLDG. FOURTH & MARKET STS.
LOUISVILLE, KENTUCKY 40202


N
CR
CR
HEALTH RM
CR
LIB WK RM
LIBRARY
CR
GENL OFFICE
V
CONF RM
Multipurpose Room
STAGE
LOBBY
TCHRS RM
T
T
BK RM
GIRLS
STOR
BOYS
KITCHEN
DW
BOILER RM
STOR
CR
CR
CR
CR
CR
CR
CR
CR
CR

Floor Plan

BOTTS ELEMENTARY SCHOOL
MENIFEE CO KENTUCKY
FLOOR PLAN 0 10 20 40

LUCKETT & FARLEY
INCORPORATED
ARCHITECTS
900 WASHINGTON BLDG. FOURTH & MARKET STS.
LOUISVILLE, KENTUCKY 40202

OWENSBORO INDEPENDENT SCHOOL DISTRICT

EIGHT CLASSROOM ADDITION TO ELEMENTARY SCHOOLS

GENERAL DESCRIPTION:

Size of Site	Existing site
Water and Sewage	Available to Existing school
Grades Housed	4 Through 6
Student Capacity	200 to 240 Students
Type Heat	Connected to existing school's hot water system.
Extent and Type of Cooling	Cooled with unit ventilators and connected to existing school's chilled water cooling.
Area in Square Feet	10,500
Construction Cost Per Sq. Ft.	$10.30*
Total Construction Cost	$108,900*
Architects	Max W. Bisson, Architects & Associates, Owensboro, Kentucky
Engineers	Waldron, Batey and Wade, Inc., Owensboro, Kentucky
General Contractor	Hartz Brothers, Owensboro, Kentucky
Date Construction Contract	Construction started March 1964
Date Completed	September 1964

Special Features - This scheme has been used by this school system very successfully where more classrooms only are needed. The existing schools contain the original classrooms and all other facilities such as library, administration, kitchen, cafeteria and multi-purpose area.

This cluster of eight classrooms is for upper grades. They all enter into the center multi-purpose area which is used for audio visual, groupings, classes and other activities.

Folding partitions are used between classrooms. These are sound-proof and electrically operated. The areas are designed for team teaching and television.

*Does not include folding partitions which were $4,000 each or built-in furniture at $6,500.

Owensboro (continued)

Construction is concrete floors with vinyl asbestos tile. Pure vinyl is used in the multi-purpose room for noise purposes. This room also has skylights that can be blacked out. It is also surrounded with storage cabinets for materials and equipment that is used by all of the teachers. In the classrooms all of the cabinets, work counters, book shelves, closets, etc. are built in. Wardrobes are box type on casters which enables them to be used also as room dividers and tack boards.

Walls are masonry with glazed tile used in corridors, toilets and multipurpose area.

OWENSBORO CITY SCHOOLS

DR. KENNETH A. ESTES, SUPERINTENDENT

EIGHT CLASSROOM ADDITION TO ELEMENTARY SCHOOLS


MULTI-PURPOSE AREA
FOLDING PARTITION
FOLDING PARTITION
TOILETS
EXTERIOR DOORS
EXISTING SCHOOL

Architect
Max W. Bisson
OWENSBORO, KENTUCKY
MEMBER AMERICAN INSTITUTE OF

PIKE COUNTY SCHOOL DISTRICT

THE GEORGE F. JOHNSON ELEMENTARY SCHOOL

GENERAL DESCRIPTION:

Size of Site	11 Acres
Water and Sewage	Water from drilled well packaged sewage treatment plant
Grades Housed	1 Through 6
Student Capacity	540
Type Heat	Hot water - unit ventilators - coal boiler
Extent and Type of Cooling	Cooling in Library, Office area, and Music - Drama Room
Area in Square Feet	33,180
Construction Cost Per Sq. Ft.	$16.87
Total Construction Cost	$559,866
Architects	Chrisman & Miller, Lexington, Kentucky
Engineers	Guy Carter, Lexington, Kentucky
General Contractor	J. I. Cornett, Elizabethton, Tennessee
Date Construction Contract	Construction started July 1966
Date Completed	September 1967

Special Features - Designed for compactness with Library or Materials Center as focus for classroom areas. Grades One, Two and Three provided with folding partitions for flexibility of instruction. Stage and Music-Drama Room placed adjacent to Arts and Crafts Room for multi-use of these areas in a coordinated program of special instruction. All windows in building are glass jalousie for sun shading and vandalism protection. All fire resistive construction with concrete slab on grade, concrete block or concrete block and brick bearing walls, steel joist roof with light-weight concrete deck and bonded built-up roof, two-hour fire rated acoustical lay-in type acoustical ceilings throughout with flush type fluorescent light fixtures.


PROPERTY LINE
PAVED PARKING
SERVICE
BUS LOADING
SEWAGE PLANT
FLAG POLE
OUTDOOR ACTIVITY
EXIT
ENTRY
KENTUCKY HIGHWAY NO. 1469
2MI. TO VIRGIE

SITE PLAN

GEORGE F. JOHNSON ELEMENTARY SCHOOL

LONG FORK OF SHELBY CREEK · PIKE COUNTY · KENTUCKY

scale 0 50 100

CHRISMAN · MILLER · ARCHITECTS


GRADE ONE
CL. RM.
CL. RM.
CL. RM.
COATS
T.
J.
T.
GRADE TWO
CL. RM.
CL. RM.
CL. RM.
GRADE FOUR
CL. RM.
CL. RM.
CL. RM.
CORRIDOR
VEND. MACH.
B.
G.
MUSIC & DRAMA
ARTS & CRAFTS
CORRIDOR
GUID.
BOOK STOR.
MECH
TEACH. WORK ROOM
CONF.
ST.
WORK AREA
LIBRARY
JAN.
CORRIDOR
CL. RM.
CL. RM.
CL. RM.
GRADE FIVE
OUTDOOR ACTIVITY
ST.
ST.
STAGE
COAL
MECHANICAL
RECPT.
W.
M.
CLINIC
AUDIO-VISUAL
PRIN.
PARKING
JAN.
STOR.
CORRIDOR
KITCHEN
DISH WASH
MULTI-PURPOSE
LOBBY
CL. RM.
CL. RM.
CL. RM.
B.
G.
SERVICE
EMP.
REF.
FRE.
GRADE THREE
CL. RM.
CL. RM.
CL. RM.
GRADE SIX
GAR.
FOOD STOR.
MAIN ENTRY
BUS LOADING — CANOPY OVER
DRIVE

FLOOR PLAN

GEORGE F. JOHNSON ELEMENTARY SCHOOL

LONG FORK OF SHELBY CREEK · PIKE COUNTY · KENTUCKY

scale 0 25 50

CHRISMAN · MILLER · ARCHITECTS

HIGH
SCHOOLS

ASHLAND INDEPENDENT SCHOOL DISTRICT

PAUL G. BLAZER SENIOR HIGH SCHOOL

GENERAL DESCRIPTION:

Size of Site	35 Acres
Water and Sewage	Provided by city
Grades Housed	10 Through 12
Student Capacity	1,650
Type Heat	Gas-fired hot water to unit ventilators
Extent and Type of Cooling	100% outdoor air mechanically forced to all areas in all buildings. No refrigeration used.
Area in Square Feet	161,450
Construction Cost Per Sq. Ft.	$14.86
Total Construction Cost	$2,399,266
Architects	Joseph Baker and Associates, Newark, Ohio
Engineers	Ralph J. Kramer, Comer and Passe
General Contractor	Werner Construction Company
Date Construction Contract	September 1961
Date Completed	Occupied September 1963

Special Features - The site is a small mountain near the center of the City of Ashland. It was underlaid with coal and rock and covered with virgin hardwood trees. It was vacant because it was considered too precipitous to build upon.

The solution used was to drill concrete piers to rock, cutting off the tops at a height to provide a flat slab that would just reach the hill of the high side. No earth was excavated, nor were any trees removed except when they fell within a building. The Olympic swimming pool was a gift of Paul Blazer.



PAUL G. BLAZER SENIOR HIGH SCHOOL ASHLAND, KY.


INSTRUMENTAL
VOCAL
ARTS AND CRAFTS
TOILETS
HEALTH LAB
FUTURE AUDITORIUM
NORTH
FLOOR PLANS

BOONE COUNTY SCHOOL DISTRICT

OCKERMAN JUNIOR HIGH SCHOOL

GENERAL DESCRIPTION:

Size of Site	33¼ Acres
Water and Sewage	City services available to property line
Grades Housed	7 Through 9
Student Capacity	1,020
Type Heat	Hot water (gas fired)
Extent and Type of Cooling	Air-conditioning in Library
Area in Square Feet	72,750
Construction Cost Per Sq. Ft.	$12.50
Total Construction Cost	$907,772.00*
Architects	Fisk, Rinehart & Hall McAllister, Stockwell
Engineers	Same as above
General Contractor	Robert T. Klensch, Inc.
Date Construction Contract	November 1964 (1st stage) April 1966 (addition)
Date Completed	December 1965 (1st stage) September 1966 (addition)

*Cost figure includes Kitchen Equipment and Lockers, but excludes Library, Shop, Home Economic and Laboratory Furnishings, Land Cost and Fees.


PLAYGOUND
NORTH
0 50 100 150 200
OCKERMAN
JUNIOR HIGH SCHOOL
FLORENCE
KENTUCKY
FISK—RINEHART
&
HALL—McALLISTER—STOCKWELL
Architects
Engineers
Cincinnati, Ohio — Covington, Kentucky

SITE PLAN

OCKERMAN JUNIOR HIGH SCHOOL

FISK–RINEHART
&
HALL–McALLISTER–STOCKWELL
Architects — Engineers
Cincinnati, Ohio — Covington, Ky.


C
B
G
S
BIO.
LIB.
I.A.
H.E.
K
L.R.
L.R.
M.E.
CAFE.
ST.
GYM.
G
B
E.L.
O
T.L.
I
B.R.
N
(FUTURE)

C–CLASSROOM
B.R.–BAND ROOM
GYM.–GYMNASIUM
B–BOY'S TOILET
G–GIRL'S TOILET
CAFE.–CAFETERIA
E.L.–ENTRANCE L'BY
L.R.–LOCKER ROOM
I.A.–INDUSTRIAL ARTS
H.E.–HOME ECONOMICS
T.L.–TEACHER'S LOUNGE
M.E.–MECHANICAL EQUIPMENT
I–INFIRMARY
K–KITCHEN
LIB.–LIBRARY
O–OFFICE
S–SCIENCE
BIO.–BIOLOGY
ST.–STAGE

CAMPBELL COUNTY SCHOOL DISTRICT

CAMPBELL COUNTY HIGH SCHOOL

PHYSICAL EDUCATION, CAFETERIA AND ADMINISTRATIVE BUILDING

GENERAL DESCRIPTION:

Size of Site	15 Acres
Water and Sewage	Municipal water supply School maintains own sewage treatment plant on site.
Grades Housed	9 Through 12
Student Capacity	1,200 (no expansion anticipated on this site)
Type Heat	Gas fired, forced hot-water heating system distributed through unit ventilators.
Extent and Type of cooling	Administration area is heated and cooled with self-contained package units.
Area in Square Feet	58,262
Construction Cost Per Sq. Ft.	$12.42
Total Construction Cost	$800,000
Architect	Edward J. Beiting, Jr. A.I.A., Newport, Kentucky
Engineer	O'Connor and Engels
General Contractor	John M. Hemmer Construction Co.
Date Construction Contract	December 1962
Date Completed	November 1963

Continued:

Special Features - Gymnasium seating capacity is approximately 3,200 persons. Cafeteria seating capacity is approximately 600 students.

In the period from June 1962 to June 1964, the Board of Education constructed a $25,000 Sewerage Treatment Plant, a $29,000 Bus Garage and a $30,000 Concrete Bleacher.

In addition to the High School, the Board of Education conducts and maintains five elementary schools, the largest of which is at Alexandria, immediately South of the High School (see Site Plan). This particular elementary school is worthy of note as it consists of six (6) buildings and was the first campus type elementary school constructed in the State.


U.S. ROUTE 27
PARKING
NEW CONCRETE BLEACHERS
FOOTBALL FIELD
CLASSROOM BUILDING
PHYS. ED., CAFETERIA AND ADMINISTRATION BUILDING
CLASSROOM BUILDING
SEWAGE TREATMENT PLANT
BUS GARAGE
WASHINGTON ST.
ORCHARD LANE
ALEXANDRIA ELEMENTARY SCHOOL

SITE PLAN FOR CAMPBELL COUNTY HIGH SCHOOL

FOR CAMPBELL COUNTY BOARD OF EDUCATION
ALEXANDRIA KENTUCKY

EDWARD J. BEITING JR. A.I.A ARCHITECT

SCALE:
0 50 100 150 200 250 300


EXISTING SCHOOL
STAIRS
STORAGE
EXISTING SCHOOL
LOBBY
RECEPTION AREA
BOARD ROOM
OFFICE
OFFICE
OFFICE
OFFICE
RECEPT.
ENTRY
T
C

FIRST FLOOR

SCALE:

0' 5' 15' 35'


UP
TOILET
STORAGE
PASSAGE
C
OFF.
OFF.
TEAM ROOM
OFFICE
FIRST AID
VARSITY LOCKERS
CAFETERIA
TOILET
C.
C.
DRYING
SHOWER
WASHING ROOM
PHYSICAL EDUCATION LOCKERS
UP
OFF.
TOILET
MUSIC DIRECTOR
WEIGHT LIFTING
UP
OFFICIALS
TOILET
STORAGE
FIRST AID
VISITOR'S LOCKERS
SHOWER
DRYING
TOILET
STORAGE
CONFERENCE RM.
DISH WASHING
REFRIG.
OFFICE
SERVICE PASSAGE
GARBAGE
DRY STORAGE
KITCHEN
EMPLOYEE LOCKER
TOILET
CHORAL ROOM
CORRIDOR
CORRIDOR
EXISTING SCHOOL
STORAGE
STORAGE
STORAGE
LOWER LOBBY
WOMEN'S LAV.
FOYER
FOYER
C
MEN'S TOILET
AREA WELLS
WOMEN'S TOILET
MUSIC RM.
CONCESSION
STORAGE

GROUND FLOOR

SCALE:

0' 5' 15' 35'

FAYETTE COUNTY SCHOOL DISTRICT

TATES CREEK SENIOR HIGH SCHOOL

GENERAL DESCRIPTION:

Size of Site	47 Acres
Water and Sewage	Municipal water, sewage and gas
Grades Housed	10 Through 12
Student Capacity	1,200
Type Heat	Hot water from central heating plant, with unit ventilators. Duct system in interior areas. Provision for future air-conditioning.
Extent and Type of Cooling	Provision for future air-conditioning
Area in Square Feet	112,000
Construction Cost Per Sq. Ft.	$12.75
Total Construction Cost	$1,474,203.25 (includes all equipment, paving and site work)
Architects	Johnson - Romanowitz
Engineers	Staggs and Fisher Mechanical Engineers White, Walker & McReynolds Structural Engineers
General Contractor	William Teater and Company
Date Construction Contract	Construction started May 1964
Date Completed	September 1966

Special Features - One of the generating factors in the design of this building is a complete structural frame consisting of precast concrete columns supporting a steel roof structure. The lack of loadbearing partitions permits free movement of most of the partitions within the building as educational needs change.

Footnote:

Page 96 gives data for student center building.


TATES CREEK HIGH SCHOOL




athletic field
junior high school
student center
senior high school
parking
elementary school
playground
greentree road
scale 0 200'
N

TATES CREEK CAMPUS
SITE PLAN

TATES CREEK SCHOOL CAMPUS
FAYETTE COUNTY, KENTUCKY
Brock, Johnson and Romanowitz
Architects Lexington, Kentucky


band
industrial arts
art
choral
mech.
auditorium
lobby
administration
commons
radio t.v.
materials center
classrooms
business ed.
typing
home ec.
classrooms

FLOOR PLAN
scale

TATES CREEK SENIOR HIGH SCHOOL
FAYETTE COUNTY, KENTUCKY
Brock, Johnson and Romanowitz
Architects Lexington, Kentucky

FAYETTE COUNTY SCHOOL DISTRICT

TATES CREEK STUDENT CENTER BUILDING

GENERAL DESCRIPTION:

Size of Site	47 Acres
Water and Sewage	Municipal water, sewage and gas
Student Capacity	Gymnasium - 2,500 seats Cafeteria - 800 seats
Type Heat	Hot water from central heating plant, with unit ventilators in Cafeteria area, unit heater in Gym.
Area in Square Feet	54,700
Construction Cost Per Sq. Ft.	$13.37
Total Construction Cost	$740,308.40 (includes all equipment, paving and site work)
Architects	Johnson - Romanowitz
Engineers	Staggs & Fisher, Mchanical Engineers White, Walker, McReynolds, Structural Engineers
General Contractor	C. Standafer Construction Co.
Date Construction Contract	Construction started March 1965
Date Completed	February 1966

Special Features - The gymnasium is designed around the use of folding bleachers on balconies provided above the first floor dressing room areas, thereby providing 4,200 sq. ft. of additional physical education space when bleachers are retracted.


heating plant
team locker
jr. high boys
sr. high boys
mech.
kitchen
serving
serving
gymnasium
lobby
dining
jr. high girls
sr. high girls
bus loading canopy

FLOOR PLAN

scale

TATES CREEK STUDENT CENTER BUILDING
FAYETTE COUNTY, KENTUCKY
Brock, Johnson and Romanowitz
Architects Lexington, Kentucky

GARRARD COUNTY SCHOOL DISTRICT

GARRARD COUNTY HIGH SCHOOL

GENERAL DESCRIPTION:

Size of Site	36 3/4 Acres
Water and Sewage	Municipal water, sewage and gas
Grades Housed	9 Through 12
Student Capacity	960
Type Heat	Hot water system, unit ventilators
Extent and Type of Cooling	Air-conditioning in auditorium. Air system with an air cooled packaged air-conditioning unit.
Area in Square Feet	112,000
Construction Cost Per Sq. Ft.	$12.27
Total Construction Cost	$1,470,728.07 (includes all equipment, paving and site work)
Architects	Johnson - Romanowitz
Engineers	Staggs & Fisher, Mechanical Engineers White, Walker & McReynolds, Structural Engineers
General Contractor	Fain and Johnston, Inc.
Date Construction Contract	Construction started July 1963
Date Completed	October 1964



GARRARD


classroom wing
school building
parking
athletic field
service area
auditorium
gymnasium
kitchen cafeteria
SITE PLAN
scale
maple avenue

GARRARD COUNTY HIGH SCHOOL
GARRARD COUNTY, KENTUCKY
Brock Johnson and Romanowitz
Architects Lexington, Kentucky


FLOOR PLAN
scale
two story
classroom wing
mech.
ind. arts
agr. shop
art
library
home ec.
auditorium
stage
girls loc.
boys loc.
choral
band
gymnasium
team loc.
administration
cafeteria
kitchen
bus loading
bus loading

GARRARD COUNTY HIGH SCHOOL
GARRARD COUNTY, KENTUCKY
Brock Johnson and Romanowitz
Architects Lexington, Kentucky

HARLAN COUNTY SCHOOL DISTRICT

JAMES A. CAWOOD HIGH SCHOOL

GENERAL DESCRIPTION:

Size of Site	25 Acres
Water and Sewage	Sewage disposal plant. City water supply -- 8" service line.
Grades Housed	9 Through 12, Gym, Auditorium, Cafeteria, Library.
Student Capacity	750 (classroom wing planned to expand to the West)
Type Heat	Unit ventilators for heating and air-conditioning
Extent and Type of Cooling	All classroom areas and auditorium
Area in Square Feet	97,000
Construction Cost Per Sq. Ft.	$13.37
Total Construction Cost	$1,297,000.00
Architects	Gray and Coblin, Architects
Engineers	White, Walker & McReynolds, Structural Engineers Staggs & Fisher, Mechanical Engineers
General Contractor	Forbes-Morris Building Company, Lexington, Kentucky
Date Construction Contract	August 26, 1964
Date Completed	August 1966

Continued:

Special Features - The Site problem was that unstable soil conditions required the use of drilled concrete filled piers with grade beams.

Carpeting was installed in the Library and Administration Area. All areas have acoustical treatment. Gym has a wood Lamella Dome.

Service facilities were designed for future expansion of the classroom area.

The building was designed very compactly for air-conditioning. Most partitions are non-bearing for maximun flexibility. Dr. John W. Gilliland, School Planning Laboratory, University of Tennessee was the Educational Consultant. A proper environment for learning was given every consideration.



Harlin County High School Gray and Coblin Archs.



Harlin County High School

JEFFERSON COUNTY SCHOOL DISTRICT

JEFFERSONTOWN HIGH SCHOOL

GENERAL DESCRIPTION:

Size of Site	32 Acres
Water and Sewage	Provided by city
Grades Housed	9 Through 12
Student Capacity	1,200
Type Heat	Unit ventilators
Extent and Type of Cooling	Academic section air-conditioned for summer use.
Area in Square Feet	118,904
Construction Cost Per Sq. Ft.	$14.36
Total Construction Cost	$1,708,157.00
Architects	Hartstern, Schnell, Associates, Louisville, Kentucky
Engineers	E. R. Ronald & Associates, Mechanical Engineer
General Contractor	Sullivan and Cozart, Inc.
Date Construction Contract	November 2, 1965
Date Completed	August 15, 1966

EDUCATIONAL PROGRAM

Organizational Plan

The organizational plan in this community is elementary school, grades one thru six, and junior and senior high school, grades seven thru twelve.

The Instructional Program

The following type of facility is provided in this building during its first phase of instruction: (a) Core (b) P.E. (c) Home Ec. (d) Shop (e) Math (f) Science (g) Art (h) Instrumental and Vocal Music (i) Remedial Reading (j) Educable Mental Retardation Training (with separate toilet facilities) (k) Improved Study skills (l) Students who perform on or above grade level will receive Math via ETV. Formal training in Foreign Languages will be accomplished either by traditional methods or by ETV. (m) Intramural activities will be provided. (n) Co-curricular activities will also be provided.

Design Criteria

This High School, located in Kentucky on a 32 acre site fronting on a county thoroughfare and surrounded by subdivisions, is designed as a junior-senior high school with an ultimate capacity of 2,200 students. This design is broken down into two initial stages: the first phase, a senior-junior high school with a capacity of 1,200 pupils with the required instructional areas to graduate a senior class. This phase includes the Physical Education Plant, Boiler and Mechanical Room, Cafeteria and Kitchen, Library, Band Room, Choral Music Rooms and Shop Rooms, all designed for the ultimate enrollment.

The second phase, a junior high school, with a capacity of 800, is planned to house only the junior high section. This section will have a separate entrance and administrative section but will use the dual facilities outlined herein.

The planning of this building is such that when Phase 2 is complete, the senior and junior high school sections will be distinctly separate but will share such dual purpose facilities as follows: Kitchen and Cafeteria - Library - Physical Education Plant - Industrial Arts - Band and Choral Music.

SITE CONSIDERATION

Education Program Continued

The Library and Physical Education Plant are so located that they can be utilized to serve the community without opening the entire school building. Material centers with conference study rooms are located on each floor to reduct the load of the Library and give better student-teacher participation.

Mechanical facilities in Phase 1 of this project are designed to serve both phases of the total scheme.

Consideration of using this school on a year around basis necessitated conditioning the academic section for summer-winter use. This conditioning allowed a design which created an inner core of classrooms and, as a result, substantially reduced the amount of corridor and exterior walls. On the second floor, it was possible to clear span this inner core, creating an educational T.V. room and six classrooms which can be opened up by means of movable walls, creating any multiple of size of classes as the curriculum needs require. All special classrooms are located on the exterior walls and above one another wherever possible to take advantage of mechanical services.

The site being located fronting a county thoroughfare and surrounded by densely populated subdivisions provides a means of separating the auto traffic from bus traffic resulting in a smoother and safer traffic flow. The bus loading at the rear of the building also better serves the population from the surrounding subdivisions. This area is connected to all points of the building by a covered walkway.

The addition of Phase 2 will complete a central court serving as outdoor classrooms for both junior and senior high art students as well as adding environment to both the Library and the Cafeteria.

The site is planned for ample parking to serve present and future needs of both teachers and students and the outdoor play area serves as overflow parking for extra-curricular activities. Since the play area's size is that of a regulation football field, it can be used in inclement weather for marching band practice.

BUILDING DESCRIPTION

The building construction is reinforced concrete skeleton frame with exposed architectural concrete columns and beams. The exterior walls are of face brick and masonry block with the typical classroom provided with aluminum sash. The academic section is two stories, with all other areas being one story. All sash are glazed with gray glass or plastic.

Academic Section - The Administrative office section has vinyl asbestos floors, painted masonry block walls and suspended acoustical tile ceiling. The cafeteria has quarry tile floor with glazed tile partitions and suspended acoustical tile. The kitchen floor slab is covered with quarry tile, walls are glazed tile and ceiling is painted concrete. All other floors are finished primarily with vinyl asbestos or ceramic tile. All partitions are masonry block painted, except the restrooms which have an epoxy glazed coating. All ceilings are incombustible acoustical tile. All corridor walls and walls in heavy traffic areas are painted an epoxy glazed coating.

Physical Education Section - Steel rigid frames are used structurally with purlins and subpurlins of steel. The underside of the structural system is covered with fireproofing. A wood fiber roof deck, acoustically treated with built-up tar and gravel roof is provided over the spacious spectator gymnasium seating two thousand four hundred. The floors of the dressing rooms, shower rooms, varsity and junior varsity rooms, toilets, etc. are concrete with a floor hardener or ceramic tile. Partitions are glazed tile and the ceiling is painted concrete. The roof construction for all shower and dressing rooms is concrete columns, beams and slabs with built-up tar and gravel roof over rigid insulation.

The choral music and band rooms have acoustical treatment on the walls and ceiling.

The physical education section and the industrial arts and music sections are connected to the academic sections by covered walkways which also lead to the building from the bus loading area.

The academic building is heated and air cooled by means of unit ventilators supplied with hot water from a combination gas and oil fired boiler and with chilled water from a central centrifugal compressor located in the main boiler room. These facilities make this building usable as an area summer school, and allow usage on a year around basis. The band and choral rooms and shops are also air-conditioned. All other sections are heated and ventilated.




GALENE DRIVE
CALAIS DR.
SCHOOL BUS AREA
FUTURE
FUTURE
FUTURE
OUTDOOR PLAY AREA
BLEACHERS
BLEACHERS
PARKING
PARKING (FUTURE)
OLD SIX MILE LANE
PHASE ONE
PHASE TWO
SITE PLAN
0
200
JEFFERSONTOWN HIGH SCHOOL
HARTSTERN SCHNELL ASSOCIATES AIA
A R C H I T E C T S


ROOM LEGEND
1 TYPICAL CLASSROOM
2 TOILET
3 TEACHERS LOUNGE
4 CLOTHING CENTER
5 DRESSING ROOM
6 LIVING SUITE
7 PANTRY
8 FOODS CENTER
9 GIRLS TOILET
10 BOYS TOILET
11 MAINTENANCE COURT
12 BOILER ROOM
13 JANITORS ROOM
14 STAFF CONFERENCE ROOM
15 TEACHERS - AIDS
16 CONFERENCE ROOM
17 LECTURE AREA
18 COUNSELOR
19 GIRLS SICK ROOM
20 HEALTH OFFICE
21 SECRETARY
22 OFFICE
23 PRINCIPAL
24 ASSISTANT PRINCIPAL
25 MAIL - MIMEO ROOM
26 MECHANICAL ROOM
27 SOUND ROOM
28 VAULT
29 STORAGE
30 CLERKS SPACE
31 WAITING ROOM
32 RECORD CLERK
33 RECORD STORAGE
34 LOBBY
35 CORRIDOR
36 PASSAGE
37 STAIRWELLS
38 AUDIO - V ON
39 PROJECTION ROOM
40 ART ROOM
41 SUPPLY ROOM
42 BOOK STORE
43 JANITORS SUPPLIES
44 CAN WASH
45 KITCHEN
46 SERVING LINE
47 SCULLERY
48 CAN WASH
49 STUDY HALL
50 OUTSIDE COURT
51 LIBRARY
52 MAGAZINE STORAGE
53 WORK ROOM
54 BOOK STORAGE
55 LOST - FOUND
56 INDUSTRIAL CENTER
57 GIRLS DRESSING ROOM
58 P.E. STORAGE
59 HEALTH ROOM
60 CONCESSIONS
61 STAGE
62 GYMNASIUM
63 TICKET OFFICE
64 BOYS DRESSING ROOM
65 SHOWER
66 TRAINING ROOM
67 VARSITY ROOM
68 CHORAL MUSIC
69 PRACTICE
70 BAND ROOM
71 JR HIGH SHOP
72 FINISH ROOM
73 GENERAL SHOP
74 MECHANICAL DRAWING RO
75 SHOP SUPPLIES
76 CAFETERIA
CAPACITY
FIRST PHASE
NO PUPILS
SQ FT
SQ FT/PUPIL
CU FT
CLASSROOM SQ FT
COVERED WALK SQ FT 3408
AREA LEGEND
FIRST PHASE
SYMBOL
AREA
BASIC EDUCATIONAL SERVICE AREA
AUXILIARY EDUCATIONAL SERVICE AREA
TRAFFIC SERVICE AREA 17.30
HEALTH SERVICE AREA
ADMINISTRATIVE SERVICE AREA
GENERAL SERVICE AREA
COMBINED PHASES
BASIC EDUCATIONAL SERVICE AREA 28.50
AUXILIARY EDUCATIONAL SERVICE AREA
TRAFFIC SERVICE AREA 23.50
HEALTH SERVICE AREA 12.10
ADMINISTRATIVE SERVICE AREA 3.30
GENERAL SERVICE AREA
100.0%
JEFFERSON COUNTY BOARD OF EDUCAT
JEFFERSONTOWN HIGH SCHO
JEFFERSONTOWN KENTUC
FUTURE ADDITION
FUTURE ADDITION
FUTURE ADDITION
COVERED WALKWAY
COVERED WALKWAY
SEATING CAPACITY 2800
FUTURE CAFETERIA CAPACITY - 280
CAPACITY - 280
50

FIRST FLOOR PLAN


FUTURE ADDITION
ROOF
ROOF
ROOF
ROOF
FUTURE COVERED WALKWAY
COVERED WALKWAY
FUTURE ADDITION
FUTURE ADDITION
ROOF
COURT
ROOF
CAPACITY - 100
CAPACITY - 100
ROOM LEGEND
77 GENERAL SCIENCE ROOM
WORK ROOM
SPECIAL EDUCATION
CHEMISTRY ROOM
TV ASSEMBLY ROOM
PHYSICS ROOM
BIOLOGY ROOM
PROJECT ROOM
INSTRUCTIONAL CENTER
TEACHERS STATION
JEFFERSON COUNTY BOARD OF EDUCATION
JEFFERSONTOWN HIGH SCHOOL
JEFFERSONTOWN KENTUCKY
HARTSTERN SCHNELL ASSOCIATES A.I.A
A R C H I T E C T S
0
50

SECOND FLOOR PLAN

MARTIN COUNTY SCHOOL DISTRICT

MARTIN COUNTY HIGH SCHOOL

GENERAL DESCRIPTION:

Size of Site	74 Acres
Water and Sewage	Water provided from well. Sewer plant was not necessary.
Grades Housed	10 Through 12
Student Capacity	1,100 (Gymnasium 3,000)
Type Heat	Electric
Extent and Type of Cooling	Air-conditioning
Area in Square Feet	75,200 (Gymnasium 32,600)
Construction Cost Per Sq. Ft.	\$13.33 (Gymnasium \$9.20 ±)
Total Construction Cost	\$1,000,000.00 ± Gymnasium \$300,000 ±
Architects	M. Gibson Taylor, Jr.
Engineers	Planning Stage
General Contractor	Planning Stage
Date Construction Contract	Planning Stage
Date Completed	Planning Stage


N
GYMNASIUM BUILDING
CLASSROOM BUILDINGS
LITTLE BLACKLOG FORK
KY. 40

SITE PLAN
MARTIN CO. HIGH SCHOOL
SCALE - 1" = 200'

MARTIN COUNTY HIGH SCHOOL

HIGH SCHOOL - 1st and 2nd Floor

1. Lobby
2. Stairs
3. Assistant Principal
4. Principal's Office
5. Secretary
6. Vault
7. Women's Toilet
8. Men's Toilet
9. Teacher's Lounge
10. Health
11. Guidance
12. Waiting
13. Typing Classroom
14. Business Machine
15. Bookkeeping
16. Classroom
17. Girl's Toilet
18. Boy's Toilet
19. Cafetorium
20. Stage Area
21. Storage
22. Janitor
23. Kitchen
24. Bookkeeping Office
25. Kitchen Office
26. Help's Dressing
27. Utility
28. Garbage Room
29. Food Storage
30. Mechanical
31. Cooking Room
32. Living Room
33. Fitting Room
34. Sewing Room
35. Home Ec. Classroom
36. General Storage
37. Home Ec. Office
38. Biolgy
39. Storage
40. Dark Room
41. Physics and Chemistry
42. English Classroom
43. English Office
44. Language Lab
45. Math Classroom
46. Math Office
47. Social Science Classroom
48. Social Science Office
49. General Science Classroom
50. General Science Office
51. Library
52. Library Work Room
53. Conference Room
54. Study Hall

Gymnasium -

1. Planning Room
2. Industrial Arts Shop
3. Finishing Room
4. Material Storage
5. Athletic Storage
6. Coach's Office
7. Corridors
8. Boy's Dressing Room
9. Toilet
10. Office
11. Practice Room
12. Gym
13. Lobby
14. Tickets
15. Boy's Toilet
16. Girl's Toilet
17. Vo-Ag Classroom
18. Vo-Ag Shop
19. Paint Shop
20. Girl's Dressing Room
21. Band Storage
22. Band Room
23. Athletic Area & Bleachers
24. Classroom
25. Physical Ed.
26. Mechanical
27. Physical Ed. Office
28. Storage
29. Art
30. Vestibule
31. Stairs


163'-6"
2
16
17
18
21
22
20
28
27
9
26
25
29
30
2
13
18
31
14
15
19
23
33
32
13
24
9
10
38
17
18
37
34
11
12
8
7
6
5
11
9
4
3
2
1
36
35
200'-2"

FIRST FLOOR PLAN MARTIN COUNTY HIGH SCHOOL

SCALE 1" = 40'

STATE OF KENTUCKY
M. GIBSON
TAYLOR, JR.
378
REGISTERED
ARCHITECT


2
47
18
17
47
47
47
47
47
2
45
46
48
39
54
49
38
45
45
39
50
40
39
163'-6"
45
45
51
49
45
45
52
38
39
53
39
17
18
43
42
39
44
42
2
42
42
42
41
2'00'-2"

SECOND FLOOR PLAN MARTIN COUNTY HIGH SCHOOL
SCALE 1" = 40'

STATE OF KENTUCKY
M. GIBSON
TAYLOR, JR.
378
REGISTERED
ARCHITECT


8
10
11
11
22
21
20
31
9
9
31
6
3
4
7
2
1
12
14
13
14
31
31
14
7
19
18
10
4
17
16
15
164'-2"
200'-2"

FIRST FLOOR PLAN MARTIN COUNTY HIGH SCHOOL GYMNASIUM

SCALE 1" = 40'

M. GIBSON
TAYLOR, JR.
378


24
30
26
25
27
26
30
24
31
31
23
12
23
24
28
29
28
24
31
31
164'-2"
200'-2"

SECOND FLOOR PLAN MARTIN COUNTY HIGH SCHOOL GYMNASIUM

SCALE 1" = 40'

STATE OF KENTUCKY
M. GIBSON
TAYLOR, JR.
378
REGISTERED
ARCHITECT

MONTGOMERY COUNTY SCHOOL DISTRICT

MONTGOMERY COUNTY HIGH SCHOOL

GENERAL DESCRIPTION:

Size of Site	30½ Acres
Water and Sewage	Provided by city
Grades Housed	10 Through 12
Student Capacity	750
Type Heat	Hot water
Extent and Type of Cooling	None
Area in Square Feet	73,000
Construction Cost Per Sq. Ft.	$11.70
Total Construction Cost	$866,000.00
Architects	M. Gibson Taylor, Jr.
Engineers	Hugh Dillehay & Assoc., Lexington, Kentucky
General Contractor	Barco, Inc.
Date Construction Contract	June 1963
Date Completed	1966


S86°25'W
566.1'
S12°16'W 34.7'
BUS GARAGE
S76°56'W
609.6'
S76°50'W
224.5'
S10°58'E
230.0'
961.7'
N 9° 00'E
HIGH SCHOOL
712.5'
S 45° 52'E
N
COUNTY
BD. OF ED
343.4'
N 8°48'E
532.1'
S68°25'E
KY. 11

SITE PLAN
MONTGOMERY CO. HIGH SCHOOL

SCALE - 1"= 300'

MONTGOMERY COUNTY HIGH SCHOOL

FIRST FLOOR PLAN

1. Physics and Chemistry
2. Storage
3. General Science
4. Biology
5. Art
6. Toilets
7. Lounge
8. Bookstore
9. Office
10. Vault
11. Closets
12. Stairs
13. Math
14. Janitor's Storage
15. Cooking
16. Living Area
17. Fitting Area
18. Sewing
19. Guidance Counselor
20. Waiting Room
21. Corridor
22. Lobby
23. Concessions
24. Ticket Booths
25. Auditorium
26. Stage
27. Dressing Rooms
28. Band Room
29. Band Storage
30. Individual Practice
31. Office
32. Boiler Room
33. Folding Partition Storage
34. Storage
35. Student
36. Lunch Room
37. Kitchen
38. Garbage
39. Help's Lockers
40. Food Storage
41. Classroom
42. First Aid
43. Gymnasium
44. Locker Rooms
45. Showers
46. Coach's Office
47. Referee's Dressing
48. Industrial Arts
49. Lumber Storage
50. Planning Room
51. Finishing Room
52. Tool Room
53. Agriculture Shop
54. Agriculture Classroom
55. Painting Room

SECOND FLOOR PLAN

56. Business Math
57. Foreign Language
58. Electives
59. English
60. Study Hall
61. Typing
62. Business Machines
63. Bookkeeping & Shorthand
64. Health
65. Social Studies
66. Library Work Room
67. Visual Aids Storage

STATE OF KENTUCKY
M. GIBSON
TAYLOR, JR.
378
REGISTERED
ARCHITECT


1
2
3
4
2
2
5
6
6
7
8
9
9
9
10
12
13
13
13
6
14
6
15
16
17
18
12
19
20
21
22
23
24
24
25
26
27
27
28
29
30
30
31
32
33
34
35
36
37
38
6
39
40
41
21
42
47
6
6
2
43
44
45
44
45
46
2
9
48
49
51
6
6
50
52
9
53
54
55

FIRST FLOOR PLAN
MONTGOMERY CO. H. S.
SCALE - 1" = 50'

STATE OF KENTUCKY
M. GIBSON
TAYLOR, JR.
378
REGISTERED
ARCHITECT


12
61
56
62
57
63
58
6
6
14
59
64
59
21
65
9
59
65
65
59
12
66
67
60
68
25
ROOF
ROOF
33
2
12
COVERED WALK
b
45
d

SECOND FLOOR PLAN
MONTGOMERY CO. H.S.
SCALE – 1" = 50'

OHIO COUNTY SCHOOL DISTRICT

OHIO COUNTY HIGH SCHOOL

GENERAL DESCRIPTION:

Size of Site	25 1/5 Acres
Water and Sewage	Municipal water from Bever Dam School owned sewage treatment plant
Grades Housed	9 Through 12
Student Capacity	Present enrollment 1,100 (for this capacity actually more classrooms should be added)
Type Heat	Unit ventilators with hot water
Extent and Type of Cooling	Cafeteria and administrative areas cooled with chilled water cooling. Provisions for cooling classroom area at a later date.
Area in Square Feet	94,450
Construction Cost Per Sq. Ft.	$9.95
Total Construction Cost	$940,187.02 ($107,493.74 for School equipment, $19,602 for Kitchen equipment)
Architects	Max W. Bisson, Architects and Associates, Owensboro, Kentucky
Engineers	Waldron, Batey and Wade, Inc., Hopkinsville, Kentucky
General Contractor	Alvey-Toombs Construction Company, Morganfield, Kentucky
Date Construction Contract	Construction started August 1964
Date Completed	September 1965

Special Features - All incombustible materials were used. Concrete floor construction, masonry walls, steel frame work and fiber tectum roof deck. Floor finishes are vinyl asbestos with terrazzo used in cooridors, kitchen, cafeteria, toilets, showers, etc. Walls are brick exterior with concrete block interior and glazed tile in corridors, cafeteria, kitchen, toilets, showers, etc. Ceilings are acoustical tile in most areas.

A center second floor section was used to eliminate long distances and to get a more composite plan. The future addition will complete a court and connect corridors.


116.0'
678.94'
PHYSICAL EDUCATION
SPORTS
N
STADIUM
INCOMPLETE
1058.0'
24.5 ACRES
PARKING
1869.99'
FUTURE
TO HARTFORD
860.05'
U.S. HIGHWAY # 231
SCALE: 1" = 200'
TO BEAVER DAM

OHIO COUNTY HIGH SCHOOL

WM. T. LEACH SUPT.

MAX W. BISSON ARCHITECT & ASSOCIATES
OWENSBORO, KENTUCKY


DRIVE
LIB.
SCIENCE
BIOLOGY
FUTURE
(ENCLOSES COURT)
T.
T.
MATH
SOC. SCIENCE
HEALTH
AG.
ADMIN.
PARKING
BUS LOADING
2ND FLOOR
ENGLISH
LANG.
GEN. PURPOSE
BUSINESS
T.
T.
FAC.
T.
T.
FOODS
LIV.
CLOTHING
BOILER
STO.
PAINT
AG SHOP
GIRLS LOCKER
BOYS LOCKER
SH.
DR.
T.
GYM.
STAGE
FLAM.
LUMB.
I.A. SHOP
STO.
BAND
SERVICE & PARKING
LOBBY
DIVIDER
FAC. DIN.
CONCES.
CAFETERIA
JAN.
ART
VOCAL
STO.
DR.
KITCHEN
STO.
SERV.
BUS LOADING
FOLDING BLEACHERS TWO LEVELS
SCALE: 1" = 60'
DRIVE

OHIO COUNTY HIGH SCHOOL

WM. T. LEACH SUPT.

MAX W. BISSON ARCHITECT & ASSOCIATES
OWENSBORO, KENTUCKY

PARIS INDEPENDENT SCHOOL DISTRICT

CAFETERIA - AUDITORIUM BUILDING

GENERAL DESCRIPTION:

Size of Site	1 Acre - Very limited due to other school facilities.
Water and Sewage	City of Paris
Grades Housed	Cafeteria, Auditorium, Band and Vocal Rooms for Elementary, Junior and Senior High School.
Student Capacity	Audiorium - 514, Cafeteria - 500, Band Room - 100
Type Heat	Fan-coil units with ventilation
Extent and Type of Cooling	None
Area in Square Feet	22,000
Construction Cost Per Sq. Ft.	$22.25
Total Construction Cost	$489,000.00
Architects	Gray and Coblin, Architects
Engineers	White, Walker & McReynolds, Structural Engineers Proctor-Ingels & Associates, Mechanical Engineers
General Contractor	Louis Fox, General Contractor, Lexington, Kentucky
Date Construction Contract	July 8, 1966
Date Completed	July 8, 1967

Continued:

Special Features - This is a round building with domed roof structure and concrete frame.

The site problem was an old existing classroom building had to be removed in order to construct the new building.

The band room and vocal music room have acoustical treatment on walls and ceiling with carpeting on floors. Design of interior partitions was special to obtain the proper sound loss through them to isolate the Band and Vocal Music Rooms.

The building is a multi-purpose structure with three more or less unrelated functions -- Cafeteria, Auditorium and Music Instructional Areas. The arrangement of these facilities on a very limited site, along with the necessity of relating the design of the building to existing buildings controlled the design. The shape of the structure was dictated by the areas to be housed.


EXISTING ELEMENTARY BUILDING
EXISTING GYMNASIUM

Paris Cafeteria-Auditorium Paris Kentucky Gray and Coblin Arch.


CANS
LOADING DOCK
RECEIVING
EMPLOYEES TOILET
FREEZER
REFRIGERATOR
JANITOR
KITCHEN 1120 SQ. FT.
DRY STORAGE 330 SQ. FT.
SERVING 200 SQ. FT.
SERVING 200 SQ. FT.
DISHWASHING 210 SQ. FT.
SCREEN
CAFETERIA 4940 SQ. FT.
ELEMENTARY DINING
HIGH SCHOOL DINING
FOLDING PARTITION
FOLDING STAGE
CHAIR STOR.
MEN
WOMEN
CHAIR STOR.
D.F.
D.F.
LOBBY
UP
LOUNGE
LOUNGE
UP
LOBBY
PASSAGE
B
B
A
A

FIRST FLOOR PLAN
SCALE 1/8" = 1'-0"

Paris Cafeteria and Auditorium


STAGE
STORAGE
DRESSING
INSTRUMENT STORAGE
PRACTICE
CORRIDOR
CORRIDOR
ORCHESTRA
CHORAL MUSIC
AUDITORIUM
BAND
OFFICE
PRACTICE
UNIF. STOR.
CORRIDOR
CORR.
OFFICE
LOBBY
PROJECTION
LOBBY

SECOND FLOOR PLAN
SCALE: 1/8" = 1'-0"

Paris Cafeteria and Auditorium

WASHINGTON COUNTY SCHOOL DISTRICT

SPRINGFIELD HIGH SCHOOL*

GENERAL DESCRIPTION:

Size of Site	33½ Acres
Water and Sewage	Municipal supply - Public sewers
Grades Housed	9 Through 12
Student Capacity	240 (Future addition may be added to the west end of building.)
Type Heat	Gas-fired hot water
Extent and Type of Cooling	None
Area in Square Feet	39,000
Construction Cost Per Sq. Ft.	$10.73
Total Construction Cost	$418,520.40
Architects	Thomas J. Nolan & Sons, Louisville, Kentucky
Engineers	Same as above
General Contractor	Ernest Simpson Construction Company, Glasgow, Kentucky
Date Construction Contract	September 29, 1961
Date Completed	May 3, 1963

Special Features - An addition is now under construction at this school.

*Merged with Washington County in 1963.



SPRINGFIELD HIGH SCHOOL

THOMAS J.NOLAN and SONS • ARCHITECTS


N
TRACK
FOOTBALL
DIAMOND
SPRINGFIELD HIGH SCHOOL
℄ LINCOLN PARK ROAD

SPRINGFIELD HIGH SCHOOL
WASHINGTON COUNTY BOARD OF EDUCATION
THOMAS J NOLAN and SONS • Architects


LOBBY
GYMNASIUM
GIRLS LOCKER
BOYS LOCKER
GEN OFFICE
OFFICE
CONFERENCE
BOOK ROOM
CLASS ROOM
CLASSROOM
CLASSROOM
CLASS ROOM
COMMERCIAL
TEACHERS LOUNGE
WORK ROOM
LIBRARY
CLASSROOM
STAGE
GIRLS TOILET
BOYS TOILET
CORRIDOR
CLASSROOM
PREP RM
SCIENCE ROOM
CLASSROOM
HOME ECONOMICS

SPRINGFIELD HIGH SCHOOL
SPRINGFIELD CITY SCHOOLS
THOMAS J NOLAN and SONS ; Architects

WOODFORD COUNTY SCHOOL DISTRICT

WOODFORD COUNTY HIGH SCHOOL

GENERAL DESCRIPTION:

Size of Site	22 Acres
Water and Sewage	Water, gas and sanitary sewers available at the site.
Grades Housed	9 Through 12
Student Capacity	1,000 (with basic facilities to accommodate an addition that will increase the capacity to 1,500)
Type Heat	Gas-fired hot-water boilers with unit ventilators in all classrooms.
Extent and Type of Cooling	Part of the building is air-conditioned
Area in Square Feet	105,034
Construction Cost Per Sq. Ft.	$11.84 (including site work and all kitchen and built-in equipment)
Total Construction Contract	$1,244,061.00
Architects	Luckett and Farley, Inc., Louisville, Kentucky
Engineers	Owensboro Engineering
General Contractor	Schickli Construction Company
Date Construction Contract	November 14, 1963
Date Completed	September 1964

Special Features - The Architects assisted the owner with both the educational and building program and the plan directly reflects the program criteria. One requirement was to design a building that was as near maintenance free as possible and to remain within the $1,250,000.00 construction budget.


WOODFORD COUNTY HIGH SCHOOL
LF LUCKETT & FARLEY, INC.
ARCHITECTS
LOUISVILLE, KY.
WOODFORD COUNTY BOARD OF EDUCATION
MR. H.B. MONTAGUE, CHAIRMAN
MR. JOHN HOWARD, VICE CHAIRMAN
MRS. NORMA ARNOLD, MEMBER
MR. JOHN MITCHELL, MEMBER
MR. ROBERT PERRY, MEMBER
MR. ISAAC ROUSE, MEMBER
MR. FRANK WATTS, MEMBER
SUPERINTENDENT : MR. GAYLE HORN


N
4 LANE HIGHWAY
TRACK & FOOTBALL
CRUSHED ROCK PARKING
PAVED PARKING
BUS LOADING
COURTYARD
FUTURE ADDITION
STREET

WOODFORD CO HIGH SCHOOL
VERSAILLES KENTUCKY

SITE PLAN

SCALE 1"=200'-0"
0 50 100 150 200

LUCKETT & FARLEY
INCORPORATED
ARCHITECTS
900 WASHINGTON BLDG. FOURTH & MARKET STS.
LOUISVILLE, KENTUCKY 40202

Floor Plan


N
BAND
CHORAL
AGRIC
DFTNG
INDUSTRIAL
SEWING
CR
GENL LVNG
BOILER RM
S
ART
BUSI
BUSI
G
B
COOKING
KITCHEN
AGRI
TCHR LNGE
BK RM
B
G
HLTH
COURTYARD
LOBBY
CAFETERIA
HLTH
OFFICE
V
B
G
CR
CR
CR
CR
CR
STUDY
STOR
STAGE
CR
CR
CR
CR
CR
LIBRARY
BLEACHERS ABOVE LOCKER RMS
BOYS
GIRLS
GYMNASIUM
FIRST FLOOR
CR
CR
BIO
BIO
CHEM & PHYS
GENL SC
CR
CR
CR
CR
CR
GENL SC
SECOND FLOOR

WOODFORD CO HIGH SCHOOL
VERSAILLES KENTUCKY
FLOOR PLAN 0 20 40 80

LUCKETT & FARLEY
INCORPORATED
ARCHITECTS
900 WASHINGTON BLDG. FOURTH & MARKET STS.
LOUISVILLE, KENTUCKY 40202

ADMINISTRATIVE BUILDINGS

PIKE COUNTY SCHOOL DISTRICT

ADMINISTRATION AND SERVICES BUILDING

GENERAL DESCRIPTION:

Size of Site	5 Acres
Water and Sewage	Provided by city
Grades Housed	Staff offices and related functions Building maintenance office and shops Transportation office and bus maint.
Student Capacity	Not applicable
Type Heat	All electric heating system - High pressure dual-duct supply system from mechanical penthouse.
Extent and Type of Cooling	Electric cooling system
Area in Square Feet	Administration building -20,100 Services building - 12,400
Construction Cost Per Sq. Ft.	$23.07 (buildings only)
Total Construction Cost	$779,980 (including $30,000 exterior work)
Architects	Chrisman and Miller, Lexington, Kentucky
Engineers	Guy Carter, Lexington, Kentucky White, Walker & McReynolds, Lexington, Kentucky
General Contractor	Goodman & Preston, Pikeville, Kentucky
Date Construction Contract	Construction started July 1966
Date completed	September 1967 (Estimated)

Special Features - The Administration Building contains space for all the operations of the Pike County school system with the exception of the Departments of Transportation and Maintenance which are contained in a separate Services Building. Of special interest in the Administration Building is the central assembly-conference room area for Board meetings, teachers' conferences, and public assembly; and the Audio-visual Studio to provide for television, radio and movie production and viewing. Provisions for future expansion provide for transfer and enlargement of spaces for various functions and for additional functions. Plans for the buildings, which encompass one of the few complete administrative plants in the country, were evolved from a team effort utilizing the present school system administrative staff, the School Planning Laboratory Consultants, the State Department of Education and the Architects.


LEVISA FORK OF BIG SANDY RIVER
BUS PARKING
STAFF PARKING
BUS MAINTENANCE
STORAGE BUILDING
STORAGE BUILDING
CARETAKERS RESIDENCE
SERVICES BUILDING
ENTRY
FUTURE ADDITION
LOAD DOCK
ADMINISTRATION BUILDING
DRIVE
VISITOR PARKING
CHESTNUT STREET
U S HIGHWAY 23

SITE PLAN

ADMINISTRATION AND SERVICES BUILDINGS

PIKE COUNTY BOARD OF EDUCATION
PIKEVILLE KENTUCKY
scale 0 50 100
CHRISMAN · MILLER · ARCHITECTS


RECORDS
GENERAL BUSINESS OFFICE
PURCHASING DIRECTOR
JAN.
VAULT
M.
W.
WAIT.
ASSIST. SUPT. FINANCE
TELEPHONE EQUIP.
REF.
UP
LOBBY
PLANTING
FLAG POLE
INSTRUCTIONAL MATERIALS
ASSEMBLY & CONF. RM'S.
(FUTURE ASSEMBLY & CONF. ROOMS)
TEMP. PART.
COATS
ST.
TEL.
SECRETARY
SUPERINTENDENT
VEST.
STORAGE
CONFERENCE ROOM
DUPLICATING & MAIL
(FUTURE RESEARCH)
AUDIO-VISUAL EQUIPMENT
(FUTURE DATA MACHINES)
WAREHOUSE STORAGE
(FUTURE PROFESSIONAL LIBRARY)
LOAD DOCK
(FUTURE MAIL RM.)
(FUTURE ENTRY)
(FUTURE DUPLICATING)
(FUTURE AUDIO-VISUAL EQUIPMENT)
(FUTURE LOAD DOCK)
(FUTURE WAREHOUSE STORAGE)
(FUTURE WORK RM.)
FUTURE INSTRUCTIONAL MATERIALS
(FUTURE ENTRY)

FIRST FLOOR PLAN

ADMINISTRATION BUILDING

PIKE COUNTY BOARD OF EDUCATION

PIKEVILLE KENTUCKY

scale 0 15 30 N

CHRISMAN · MILLER · ARCHITECTS


OFFICE INSTRUCTIONAL SUPERVISORS
CORRIDOR
TESTING
GUIDANCE
ST.
UP
ST.
DUCTS
(MECH. PENTHOUSE ABOVE)
ASSIST. SUPT. INSTRUCTION
OPEN
PUPIL PERSONNEL
WAITING
(FUTURE ROOF)
CONTROL ROOM
AUDIO-VISUAL STUDIO
DUCTS
BALCONY
DN
PUPIL PERSONNEL
MATERIALS
OPEN
CENSUS
STORAGE
DUCTS
PROJ. ROOM
DUCTS
ASSIST. SUPT. GENERAL ADM.
CORRIDOR
JAN.
VENDING MACHINES
STORAGE
KIT.
OFFICE FEDERAL PROGRAMS
DIRECTOR FOOD SERVICES
SICK & FIRST AID
LOUNGE
DN
DN

SECOND FLOOR PLAN

ADMINISTRATION BUILDING

PIKE COUNTY BOARD OF EDUCATION
PIKEVILLE KENTUCKY
scale 0 10 30 N
CHRISMAN · MILLER · ARCHITECTS


BUS STALL ROOM
TIRE REPAIR
AIR COMP.
STORAGE
VENDING MACHINES
LIFT
LIFT
BENCH
BUS PAINT STALL
FINISH ROOM
CARPENTRY SHOP
T.
STORAGE
JAN.
T.
T.
MECH. ROOM
OFFICE
TOILET
OIL
LARGE PARTS STORAGE
BATTERY STORAGE
ELECTRICAL SHOP
CORRIDOR
SECRETARIES
STORAGE
PLUMBING & HEATING SHOP
PLUMBING STORAGE
MAINTENANCE SUPPLY STORAGE
DIRECTOR OF BL'DG. GROUNDS
VESTIBULE
DIRECTOR OF TRANSPORTATION
ENTRY
SMALL PARTS STORAGE
TIRE STORAGE
ELECTRIC DIST. RM.

FLOOR PLAN

SERVICES BUILDING

PIKE COUNTY BOARD OF EDUCATION
PIKEVILLE KENTUCKY
scale 0 10 20
CHRISMAN · MILLER · ARCHITECTS

VOCATIONAL
SCHOOLS

ELIZABETHTOWN INDEPENDENT SCHOOL DISTRICT

ELIZABETHTOWN VOCATIONAL SCHOOL

GENERAL DESCRIPTION:

Size of Site	10 Acres
Water and Sewage	Municipal supply - Public sewer
Student Capacity	324 (future addition may be added to either the north or south side of the building)
Type Heat	Gas-fired hot water
Extent and Type of Cooling	Partial
Area in Square Feet	31,750
Construction Cost Per Sq. Ft.	$13.62
Architects	Thomas J. Nolan & Sons, Louisville, Kentucky
Engineers	Thomas J. Nolan & Sons and Southern Engineering Company, Louisville, Kentucky
General Contractor	Robert Struck & Sons, Louisville, Kentucky
Date Construction Contract	December 1, 1965
Date Completed	July 15, 1966

Special Features - This Vocational School will provide training for students of Elizabethtown City School System as well as the Hardin County School System and all adults of the area. The administrative section, classrooms and drafting room are air-conditioned.



ELIZABETHTOWN VOCATIONAL SCHOOL
thomas j nolan : sons . architects


N
COLLEGE STREET ROAD
545'
500'
ELIZABETHTOWN
VOCATIONAL SCHOOL


WELDING
AUTO REPAIRS
BUILDING TRADES
MECH EQUIP ROOM
TOOL RM
SUPPLY RM
GEN STORAGE
TOOL RM
STORE
MEN
WOMEN
TOOL RM
CLASSROOM
CORRIDOR
STORE
TOOL ROOM
SUPPLY ROOM
TOOL ROOM
SUPPLY ROOM
SUPPLY ROOM
SUPPLY ROOM
CLASSROOM
DRAFTING SKILLS
APPLIANCE REPAIRS
ELECTRICAL
CLASSROOM
PRINCIPAL
GEN OFFICE
VESTIBULE

ELIZABETHTOWN VOCATIONAL SCHOOL
THOMAS J NOLAN and SONS • Architects

MARION COUNTY SCHOOL DISTRICT

MARION COUNTY VOCATIONAL SCHOOL

GENERAL DESCRIPTION:

Size of Site	10 Acres
Water and Sewage	Water and gas were available at the site, but sanitary sewers had to be extended a considerable distance.
Grades Housed	Not applicable
Student Capacity	182
Type Heat	Gas-fired boiler
Extent and Type of Cooling	Air-conditioned by self-contained air-conditioning unit ventilators. These self-contained air-conditioning units permit the cooling of one or all units at any time.
Area in Square Feet	24,890
Construction Cost Per Sq. Ft.	$13.58 (including all built-in equipment and site work)
Total Construction Cost	$337,900
Architects	Luckett & Farley, Inc., Louisville, Kentucky
Engineers	E. R. Ronald & Associates
General Contractor	A. D. Roe Construction Company
Date Construction Contract	February 1966
Date Completed	September 1966


MARION COUNTY
VOCATIONAL SCHOOL
MARION COUNTY VOCATIONAL SCHOOL
LEBANON, KENTUCKY
LUCKETT & FARLEY, INC.
ARCHITECTS
LOUISVILLE, KENTUCKY
MARION COUNTY BOARD OF EDUCATION


N
FUTURE ADDITION

Site Plan

MARION CO VOCATIONAL SCHOOL
LEBANON KENTUCKY
SITE PLAN

0 25 50 100 150

LUCKETT & FARLEY
INCORPORATED
ARCHITECTS
900 WASHINGTON BLDG. FOURTH & MARKET STS.
LOUISVILLE, KENTUCKY 40202


N
AUTO MECHANIC
BLDG TRADES
WELDING
MECH
G
STOR
ST
ST
B
PLANTING AREA
DRAFTING
BUSINESS ED
BUSINESS ED
CR
CR
LOBBY
ADMIN
CR

Floor Plan

MARION CO VOCATIONAL SCHOOL
LEBANON KENTUCKY
FLOOR PLAN 0 10 20 40

LUCKETT & FARLEY
INCORPORATED
ARCHITECTS
900 WASHINGTON BLDG. FOURTH & MARKET STS.
LOUISVILLE, KENTUCKY 40202

NELSON COUNTY SCHOOL DISTRICT

NELSON COUNTY VOCATIONAL SCHOOL

GENERAL DESCRIPTION:

Size of Site	46 Acres
Water and Sewage	Municipal supply - Public sewer
Student Capacity	324 (future addition may be added to either the north or south side of the building)
Type Heat	Oil fired - hot water
Extent and Type of Cooling	Partial
Area in Square Feet	39,773
Construction Cost Per Sq. Ft.	$11.37
Total Construction Cost	$452,470 (bid)
Architects	Thomas J. Nolan & Sons, Louisville, Kentucky
Engineers	Thomas J. Nolan & Sons and Southern Engineering Company, Louisville, Kentucky
General Contractor	A. D. Roe, Louisville, Kentucky
Date Construction Contract	June 30, 1966
Date Completed	Not completed

Special Features - The large acreage of this site is contemplated to also provide the new Nelson County High School which will be connected to the Vocational School by covered walkways. The administrative area as well as the three classrooms and drafting room are to be air-conditioned.



NELSON COUNTY VOCATIONAL SCHOOL Thomas JNolan and Sons - Architects


N
NELSON COUNTY
VOCATIONAL
SCHOOL
US HIGHWAY 63


BUILDING TRADES
AUTO REPAIR
WELDING
STORAGE
GEN STORAGE
MEN
WOMEN
JAN
SUPPLY
TOOLS
CONCESSION
GEN STORAGE
TOOLS
SUPPLY
BOILER
CORRIDOR
SUPPLY
SUPPLY
TOOL
SUPPLY
TOOL
SUPPLY
VAULT
BOOKKEEPING
STORE
SUPPLY
LOBBY
ENTRY
CLASSROOM
DRAFTING
GEN OFFICE
OFFICE
CLASSROOM
CLASSROOM
ELECTRICAL
APPLIANCE REPAIR

NELSON COUNTY VOCATIONAL SCHOOL
THOMAS, [illegible] and SONS • Architects

PADUCAH INDEPENDENT SCHOOL DISTRICT

PADUCAH AREA VOCATIONAL AND TECHNICAL SCHOOL

GENERAL DESCRIPTION:

Size of Site	2 3/4 Acres
Water and Sewage	City and water sewage
Grades Housed	Not applicable
Student Capacity	284
Type Heat	Gas furnace - forced air
Extent and Type of Cooling	25% air-conditioned
Area in Square Feet	41,225
Construction Cost Per Sq. Ft.	$12.95
Total Construction Cost	$534,553.64
Architects	G. Anthony Johnson & Associates, Paducah, Kentucky
Engineers	E. T. Hannan & Associates, Inc.
General Contractor	Seth E. Glen
Date Construction Contract	February 15, 1965
Date Completed	June 1, 1966

OWNER	- PADUCAH BOARD OF EDUCATION	CONSTRUCTION	LOAD BEARING MASONRY STRUCTURAL STEEL
ARCHITECT	- G. ANTHONY JOHNSTON & ASSOC.	SQUARE FOOTAGE	41,225 SQ. FT.
MECHANICAL ENGINEER	- E.T. HANNAN & ASSOC. INC.	BUILDING COST	$ 534,553.64
GENERAL CONTRACTOR	- SETH E. SIEM	COST PER FOOT	$ 12.95



PADUCAH AREA VOCATIONAL & TECHNICAL SCHOOL

PERSPECTIVE SKETCH

G. ANTHONY JOHNSTON & ASSOCIATES

ARCHITECTS
PADUCAH, KY.



JACKSON ST.
SHOPS
CLASSROOMS
&
ADMINISTRATION
24 ST.
25 ST
ADAMS ST.

PADUCAH AREA VOCATIONAL & TECHNICAL SCHOOL

SITE PLAN

SCALE
0
50
100

B. ANTHONY [illegible] ASSOCIATES ARCHITECTS
PADUCAH, KY.



ROOM INDEX

1 LOBBY
2 GENERAL OFFICE
3 OFFICE
4 DIRECTORS OFFICE
5 STORAGE
6 BLUEPRINT
7 JANITOR
8 WORK ROOM
9 MEN
10 WOMEN
11 CORRIDOR
12 DRAFTING
13 CLASSROOM
14 DEMONSTRATION
15 RELATED CLASSROOM
16 CONFERANCE ROOM
17 MECHANICAL ROOM
18 AUTO MECHANICS
19 AUTO BODY SHOP
20 ELECTRIC SHOP
21 ELECTRONICS
22 TOOLS
23 LOCKER ROOM
24 FINISHING
25 WELDING BOOTHS
26 BUILDING TRADES
27 MACHINE SHOP
28 WELDING SHOP
29 APPLIANCE REPAIR

PADUCAH AREA VOCATIONAL & TECHNICAL SCHOOL

FLOOR PLAN

G. ANTHONY JOHNSTON & ASSOCIATES

ARCHITECTS

PADUCAH, KY.

COMMONWEALTH OF KENTUCKY
Department of Education
FRANKFORT 40601

MEMORANDUM

TO: All Architects

FROM: Paul W. Thurman, Director
Buildings and Grounds

DATE: June 27, 1966

SUBJECT: Plans for School Buildings

In my memorandum to you on May 23, 1966, I asked for some materials for inclusion in the revised issue of the Kentucky Department of Education's Educational Bulletin Planning for School Plant Construction. The original timing for the publication of this bulletin was for October 1966. However, since my last memorandum to you, this date has been moved up. Requests to me now are to have all material ready for a September publication. This means I will have to ask you to submit any material you wish to include by no later than August 1, 1966.

Some of you have made inquiries as to the amount of material or numbers of buildings that we can include from each architect. I am sorry that I cannot give you a definite answer at this time, however, if possible, we plan to publish all work submitted. As this block of time since January 1963 covers many building projects, and if all were submitted, volume alone could demand some elimination. We certainly will not eliminate any architect or architectural firm but may have to include only a limited number of each type of building plans that are submitted by each architect. (By types, I am referring to trade schools, high schools, elementary schools, central office buildings, etc.)

I hope the earlier date will not inconvenience you too much and that I will be hearing from you soon.

COMMONWEALTH OF KENTUCKY

Department of Education

FRANKFORT 40601

MEMORANDUM

TO:	All Architects
FROM:	Paul W. Thurman, Director Buildings and Grounds
DATE:	May 23, 1966
SUBJECT:	Plans for Kentucky School Buildings

The Division of Buildings and Grounds will publish the October 1966 issue of the Kentucky Department of Education Educational Bulletin. The central idea of this issue is to be planning for school construction. Even though funds are not available at the present time for major construction in all districts, planning and study for future planning is always with the local school administrator.

The State of Kentucky can be extremely proud of the many fine schools that have been constructed in the last few years. Unfortunately, all school personnel do not have the opportunity to visit these plants and become acquainted with their excellent features. We, through the use of this bulletin, plan to place in the hands of all school administrators of the state some information on the buildings we presently have in the hope of helping them with their job in planning construction for the future.

With the above thought in mind, we are asking you to supply us with some material that we can use in this publication. We would like basic information on any or all new construction and/or major renovation that you have planned for Kentucky schools since January 1963. Our aim is to include samples of work from all architects doing school in Kentucky. In order for us to reproduce your work for bulletin use, we must receive it on uniform material; therefore, we are asking that all material be submitted on 81/2" X 11" white paper. All material should be as you wish it published, as we will simply reproduce your work for bulletin use.

For the purpose of uniformity, we suggest the following information be included and a method of preparation:

Page 1: General Information

Here we would like the name of the school and school district, size of the site, availability of water and sewage facilities, school organization or grades housed, student capacity, plans for expansion, type heat, extent and type of cooling, area in square feet, construction cost per square foot, total construction cost, architectural firm, consulting engineers, general contractor or contractors, and date of construction contract and date completed. Additional comments should be made as space will permit, giving information on special features, site problems involved, treatment of special areas, planned expansion, special material usage, design principles et cetera.

Page 2: Plot Plan

This should include the entire site, showing building and other improvement locations such as drives, parking, athletic fields, et cetera, an indication of general terrain should be shown.

Page 3: Floor Plan Layout

This should be a single line drawing with identification of all areas. Larger buildings will require more than one page.

We also would like information on smaller special purpose buildings such as central office facilities, bus garages, maintenance buildings, stadium seating et cetera where buildings are involved. With these smaller projects, we suggest grouping of information in order to utilize less space and for clarity of interpretation.

This, we realize, is a big request. However, without your help, we would never be able to furnish needed information to the various districts of the state. In order for us to meet a deadline, we must have any material you submit by August 15, 1966. We assure you that we will make every effort to present this work in as attractive form as possible and feel that all of us can benefit from this effort.